

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana


SOIL BORING LOG

No. B-11

FILE: 914206
DATE: Dec. 28, 2004
DRILLER: R. Warren
TECH.: M. Donald
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

SHEET 1 OF 2

FIELD DATA			LABORATORY DATA							Location: See Figure 2. Lat. 31° 23' 34.9" Long. 92° 42' 02.3" Surface Elevation: 84.4 ±		Strata Break Depth	Soil Type
Depth (feet)	Samples	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index			
	Groundwater Level			Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI	DESCRIPTION		
		1.00 (P)									Stiff brown CLAY (CH) - with roots and organics		
		1.25 (P)	1.26	118	94		14	57		43		4.0	
5	▽	0.25 (P)									Soft to very soft brown SILTY CLAY (CL)		
	▽	0.00 (P)	0.30	115	89			25					
10		0.00 (P)											
		0.00 (P)											
		2 b/18" 1-1-0									- more clayey (CL-CH) below 12'		
15		1 b/18" 0-0-1					15	38		23			
		1 b/18" 0-1-0						33				18.0	
		1.25 (P)									Firm to stiff gray CLAY (CH)		
20		1.00 (P)	0.64	106	75		18	42	86	68			
		0.75 (P)											
25		1.00 (P)											
		0.75 (P)									- dark gray below 28'		
30		0.75 (P)											
		1.25 (P)											
35		1.25 (P)											
		1.50 (P)											
		0.50 (P)											
40		0.25 (P)					17		107	150			
								64					
45		0.25 (P)											
												47.0	
											WOOD with clay		
50													
Groundwater Level Data			Advancement Method							Notes			
208 GPJ AQUATER GWT 1/3/05 First encountered at 8 ft. Rose to 5.6 ft. after 10 min.			Short-flight Auger: 0' - 10' Rotary Wash: 10' - 100'										
			Abandonment Method Hole backfilled with cement/bentonite grout upon completion.										
													

STRATA BOUNDARIES MAY NOT BE EXACT

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana


SOIL BORING LOG

No. B-11

FILE: 914206
DATE: Dec. 28, 2004
DRILLER: R. Warren
TECH.: M. Donald
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

SHEET 2 OF 2

FIELD DATA			LABORATORY DATA							Location: See Figure 2. Lat. 31° 23' 34.9" Long. 92° 42' 02.3"		Strata Break Depth	Soil Type
Depth (feet)	Samples	Groundwater Level	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index		
					Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI		
												DESCRIPTION	
												WOOD with clay (continued)	
55												58.0	
60			0.50 (P)									Firm gray very SANDY CLAY to CLAYEY SAND (CL-SC)	
65			1.25 (P)					14	23		9		
70			1.00 (P)									72.0	
75			0.50 (P)					17	22		5	Firm light gray SILTY CLAY (CL) - with sand	
80			0.25 (P)				16					77.0	
85			2.50 (P)									79.5	
90			4.50+ (P)									82.0	
95			4.50+ (P)									87.0	
100			4.50+ (P)									92.0	
								23	52		29	Hard gray CLAY (CH)	
												Boring Terminated at 100 Feet.	
												100.0	
Groundwater Level Data				Advancement Method							Notes		
<input checked="" type="checkbox"/> First encountered at 8 ft. <input checked="" type="checkbox"/> Rose to 5.6 ft. after 10 min.				Short-flight Auger: 0' - 10' Rotary Wash: 10' - 100'									
				Abandonment Method									
				Hole backfilled with cement/bentonite grout upon completion.									

1206 LP-J AQUATERRA GDT 1/2005

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

CLIENT: CLECO Corporation
Pineville, Louisiana

SOIL BORING LOG

No. B-12

SHEET 1 OF 1

FILE: 914206
DATE: Dec. 15, 2004
DRILLER: R. Warren
TECH.: J. Rummler
ENGINEER: V. Donald

FIELD DATA			LABORATORY DATA							Location: See Figure 2. Lat. 31° 23' 30.4" Long. 92° 42' 12.7"		Strata Break Depth	Soil Type
Depth (feet)	Samples	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index	DESCRIPTION		
	Groundwater Level			Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit				
		3.50 (P)									Stiff red SILTY CLAY (CL) - with roots	2.0	
		1.00 (P)									Loose red CLAYEY SILT (ML)	4.0	
5		2.00 (P)	0.70	112	85		20	31	54	34	Firm red CLAY (CH) - with silt seams		
		1.25 (P)										8.0	
10		0.75 (P)					19	28	24	9	Loose red CLAYEY SILT (ML)		
		0.50 (P)									- with sand below 12'		
15		WOH				63							
		WOH											
		WOH											
20		WOH											
		WOH											
		WOH											
30		0.75 (P)	0.28 (t)	118	92		18	31	28	15	Very soft to soft red and brown SILTY CLAY (CL)		
		WOH											
		WOH											
35		0.75 (P)											
		0.75 (P)	0.36 (t)	106	79		22	32	35	20			
		WOH											
40											Boring Terminated at 40 Feet.	40.0	
45													
50													

Groundwater Level Data

▽ First encountered at 7 ft.
No rise after 15 min.

Advancement Method

Short-flight Auger: 0' - 10'
Rotary Wash: 10' - 40'

Abandonment Method

Hole backfilled with cement/bentonite grout upon completion.

Notes

WOH: weight of hammer
t: Unconsolidated, undrained triaxial compression test at overburden pressure.

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-13

SHEET 1 OF 1

FILE: 914206
DATE: Dec. 16, 2004
DRILLER: R. Warren
TECH.: J. Rummler
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

FIELD DATA			LABORATORY DATA						Location: See Figure 2. Lat. 31° 23' 30.4" Long. 92° 42' 07.5"		Strata Break Depth	Soil Type
Depth (feet)	Samples	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index		
	Groundwater Level			Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI	DESCRIPTION	
		4.00 (P)									Firm to stiff red and brown SILTY CLAY (CL)	
		2.50 (P)	0.71	117	93		15	41		26		4.0
5		0.25 (P)									Very soft red and brown very SILTY CLAY (CL-ML)	
		<0.25 (P)					17	29		12		
		0.25 (P)										
10		0.50 (P)										
		0.50 (P)										
15	X	WOH										16.0
	X	WOH				85		28			Very loose red and brown CLAYEY SILT (ML) - with sand	
20	X	WOH										22.0
	X	WOH										
		0.50 (P)									Soft red and gray very SILTY CLAY (CL)	
5		0.75 (P)										
		0.25 (P)										
30	X	WOH	0.71	117	90		16	47		31		32.0
		1.00 (P)									Firm red and brown SILTY CLAY (CL)	
		1.50 (P)										
35		1.00 (P)										38.0
		1.00 (P)										
40	X	WOH				42		31			Very loose red and brown very SILTY fine SAND (SM-ML)	40.0
											Boring Terminated at 40 Feet.	
											STRATA BOUNDARIES MAY NOT BE EXACT	
Groundwater Level Data			Advancement Method						Notes			
First encountered at 4.6 ft Hole fell in 4.6 ft after 15 min.			Short-flight Auger: 0' - 10' Rotary Wash: 10' - 40'						WOH: weight of hammer			
			Abandonment Method									
			Hole backfilled with cement/bentonite grout upon completion.									

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-14

SHEET 1 OF 1

FILE: 914206
DATE: Dec. 27, 2004
DRILLER: R. Warren
TECH.: M. Donald
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

FIELD DATA			LABORATORY DATA							Location: See Figure 2. Lat. 31° 23' 30.4" Long. 92° 42' 02.3" Surface Elevation: 84.1 ±		Strata Break Depth	Soil Type
Depth (feet)	Samples	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index	DESCRIPTION		
	Groundwater Level			Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI			
		3.00 (P)										Stiff brown CLAY (CH)	
		3.75 (P)											
5	▽	0.00 (P)					17	27		10	Very soft brown SILTY CLAY (CL) - with sand	4.0	
		1 b/18"											
		1-0-0											
10		1 b/18"				89							
		1-0-0											
		1 b/18"											
		1-0-0											
15		1 b/18"											
		1-0-0											
		7 b/f											
		3-3-4											
20		2 b/f											
		1-1-0											
		0.00 (P)											
		0.00 (P)					15	29		14	Very loose red very SILTY fine SAND (SM)	23.0	
5		3 b/18"											
		1-2-0											
		4b/f											
		2-2-2											
30		1 b/18"											
		1-0-0											
		7 b/f											
		3-3-4											
		7 b/f											
		2-3-4											
35		5 b/f											
		2-2-3											
		19 b/f				19							
		4-7-12											
40		24 b/f											
		10-12-12											
											Boring Terminated at 40 Feet.		40.0
											STRATA BOUNDARIES MAY NOT BE EXACT		
Groundwater Level Data						Advancement Method				Notes			
▽ First encountered at 5.5 ft No rise after 15 min.						Short-flight Auger: 0' - 6' Rotary Wash: 6' - 40'							
						Abandonment Method							
						Hole backfilled with cement/bentonite grout upon completion.							



2004 AQUATERRA, GDT 1/2005
AD LOG

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana


SOIL BORING LOG

No. B-15

SHEET 1 OF 1

CLIENT: CLECO Corporation
Pineville, Louisiana

FILE: 914206
DATE: Dec. 29, 2004
DRILLER: R. Warren
TECH.: M. Donald
ENGINEER: V. Donald

FIELD DATA			LABORATORY DATA						Location: See Figure 2. Lat. 31° 23' 30.4" Long. 92° 41' 57.1"		Strata Break Depth	Soil Type
Depth (feet)	Samples	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index		
	Groundwater Level			Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI	DESCRIPTION	
		0.25 (P)									Loose red SANDY SILT (ML)	8.0
5		0.50 (P)				91						
		5 b/18" 0-2-3									Soft to firm red CLAY (CH)	8.0
10		4 b/7 2-2-2										
		0.50 (P)	0.86	108	76					61		
		1.00 (P)										
15		0.50 (P)										
		1.25 (P)										
		1.00 (P)										
20		1.50 (P)										
		1.25 (P)										
.5		1.50 (P)										
		0.50 (P)										
30		0.25 (P)										
		1.25 (P)										
		1.00 (P)										
35		0.50 (P)										
		0.50 (P)										
40		0.50 (P)										
											Boring Terminated at 40 Feet.	40.0
45												
50												
Groundwater Level Data			Advancement Method						Notes			
<input checked="" type="checkbox"/> First encountered at 5 ft <input checked="" type="checkbox"/> Hole fell in 4.5 ft after 15 min.			Short-flight Auger: 0' - 6' Rotary Wash: 6' - 40'						STRATA BOUNDARIES MAY NOT BE EXACT 			
			Abandonment Method									
			Hole backfilled with cement/bentonite grout upon completion.									

208.GPJ AQUATERRA.GDT 1/3/05

AQ LOG SOIL

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-16

SHEET 1 OF 1

FILE: 914206
DATE: Dec. 13, 2004
DRILLER: R. Warren
TECH.: J. Rummier
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

FIELD DATA			LABORATORY DATA						Location: See Figure 2. Lat. 31° 23' 30.4" Long. 92° 41' 51.9"		Strata Break Depth	Soil Type
Depth (feet)	Samples	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index		
	Groundwater Level			Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI		
		3.00 (P)										
		2.75 (P)	1.00	116	93		24	62		38		
5		1.75 (P)										
		1.75 (P)				87						
10												
		1.00 (P)	0.36	120	98		16	43		27		
15		2.75 (P)										
		3.00 (P)										
20		2.00 (P)	0.87									
		WOH										
						92						
25		1.75 (P)										
		2.00 (P)										
30		1.50 (P)										
		2.25 (P)										
		1.25 (P)	0.67	108								
35		0.75 (P)										
		1.50 (P)										
		1.75 (P)										
40												
45												
50												
Groundwater Level Data			Advancement Method						Notes			
First encountered at 9 ft. No rise after 15 min.			Short-flight Auger: 0' - 10' Rotary Wash: 10' - 40'						WOH: weight of hammer			
			Abandonment Method									
			Hole backfilled with cement/bentonite grout upon completion.									



208.GPJ AQUATERR GDT 1/3/05

AQ LOG Sheet

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-17

FILE: 914206
DATE: Dec. 14, 2004
DRILLER: R. Warren
TECH.: J. Rummier
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

SHEET 1 OF 1

FIELD DATA			LABORATORY DATA						Location: See Figure 2. Lat. 31° 23' 26.0" Long. 92° 42' 07.5"		Strata Break Depth	Soil Type
Depth (feet)	Samples	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index		
	Groundwater Level			Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI	DESCRIPTION	
5	▽	1.50 (P)	0.60	114	87		19	50	31	31	Firm to stiff red and brown slightly SILTY CLAY (CL-CH)	10.0
		1.75 (P)										
		0.50 (P)										
		1.50 (P)										
10		1.00 (P)	97 (g)								Very loose brown CLAYEY SILT (ML) - with sand	34.0
		0.00 (P)										
		0.00 (P)										
15	X	WOH										
		WOH										
		0.00 (P)										
20	X	WOH										
		WOH										
		0.00 (P)										
25	X	WOH										
		0.00 (P)	86								- more sandy (ML-SM) at 18' - 20'	
		0.00 (P)										
		0.00 (P)										
30	X	WOH										
		WOH	45 (g)								Medium dense red and gray SILTY fine SAND (SM)	40.0
		WOH										
		WOH										
35	X	24 b/f										
		4-10-14	Boring Terminated at 40 Feet.									
		35 b/f										
		8-17-18										
40	X	23 b/f										
		11-13-10										
45												
50												

Groundwater Level Data

▽ First encountered at 5 ft.
No rise after 15 min.

Advancement Method

Short-flight Auger: 0' - 10'
Rotary Wash: 10' - 40'

Abandonment Method

Hole backfilled with cement/bentonite grout upon completion.

Notes

g: see attached grain size curves

STRATA BOUNDARIES MAY NOT BE EXACT



2001 GP-1 AQUATERRA LOG 1/2/05
A3 LOG 5

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-18

SHEET 1 OF 1

FILE: 914206
DATE: Dec. 19, 2004
DRILLER: R. Warren
TECH.: M. Donald
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

FIELD DATA			LABORATORY DATA							Location: See Figure 2. Lat. 31° 23' 26.0" Long. 92° 42' 02.3"		Strata Break Depth	Soil Type
Depth (feet)	Samples	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index	DESCRIPTION		
	Groundwater Level			Moist	Dry			Plastic Limit	Moisture Content			Liquid Limit	
		1.00 (P)											
		0.75 (P)											
5		0.75 (P)	0.51	111	90		21.6	14.1	27.1	5	Loose red CLAYEY SILT (ML)	4.0	
		0.00 (P)									Very loose red CLAYEY, SANDY SILT (ML)	6.0	
10		0.00 (P)				77 (g)		27			Very soft red very SILTY CLAY (CL-ML)	10.0	
		0.00 (P)										14.0	
15		WOH									Very loose red CLAYEY, SANDY SILT (ML)		
		WOH											
		WOH											
20		WOH				64		25					
		WOH											
25		1 b/f											
		3 b/f											
		WOH											
30		8 b/f 1-1-7				66		26			- loose at 28' - 30'	30.0	
		27 b/f 7-13-14									Medium dense red SILTY fine SAND (SM)		
		4 b/f 3-1-3									- loose at 32' - 34'		
35		23 b/f 3-11-12						2					
		28 b/f 9-12-16											
40		23 b/f 9-11-12				15		23			Medium dense red SANDY SILT (ML)	38.0	
											Boring Terminated at 40 Feet.	40.0	
45													
50													

Groundwater Level Data

☒ Water at ground surface

Advancement Method

Rotary Wash: 0' - 40'

Abandonment Method

Hole backfilled with cement/bentonite grout upon completion

Notes

g: see attached grain size curves
WOH: weight of hammer

AQ LOG S.D. 706.GPJ AQUATERRA.GDT 1/3/05



PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-19

FILE: 914206
DATE: Dec. 19, 2004
DRILLER: R. Warren
TECH.: M. Donald
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

SHEET 1 OF 1

FIELD DATA			LABORATORY DATA							Location: See Figure 2. Lat. 31° 23' 26.0" Long. 92° 41' 57.1"		Strata Break Depth	Soil Type
Depth (feet)	Samples Groundwater Level	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index	DESCRIPTION		
				Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI			
		4.50 (P)											
		1.50 (P)											
5		1.25 (P)	1.27	111	83		18	34	72	54	Stiff to very stiff red CLAY (CH)	6.0	
		0.25 (P)									Soft to firm red SILTY CLAY (CL)	8.0	
10		0.00 (P)									Very loose red SANDY SILT (ML) - with clay		
		0.00 (P)				76		28					
15		1 b/f 1-1-0											
		1 b/18"											
		1 b/18"											
20		WOH				70		26					
		1 b/18" 1-1-0											
		WOH											
25		2 b/f 1-1-1											
		1 b/18" 1-1-0											
		1 b/18" 1-1-0											
30		5 b/f 2-2-3									- loose at 32' - 34'		
		2 b/f 1-1-1											
35		2 b/f 1-1-1									- loose at 36' - 38'		
		5 b/f 3-2-3									- more sandy (ML-SM) at 38' - 40'		
40		3 b/f 1-2-1				52		22			Boring Terminated at 40 Feet.	40.0	
45													
50													
Groundwater Level Data			Advancement Method							Notes			
<input checked="" type="checkbox"/> First encountered at 9 ft Rose to 8 ft. after 10 min.			Short-flight Auger: 0' - 12' Rotary Wash: 12' - 40'							WOH: weight of hammer			
			Abandonment Method										
			Hole backfilled with cement/bentonite grout upon completion										

STRATA BOUNDARIES MAY NOT BE EXACT



208.GPJ AQUATER.R.GDT 1/2/05

AQ LOG

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-20

SHEET 1 OF 1

FILE: 914206
DATE: Dec. 14, 2004
DRILLER: R. Warren
TECH.: J. Rummier
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

FIELD DATA			LABORATORY DATA						Location: See Figure 2. Lat. 31° 23' 25.9" Long. 92° 41' 51.9"		Strata Break Depth	Soil Type
Depth (feet)	Samples	Groundwater Level	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits				
					Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit		
			1.50 (P)									
			0.75 (P)									
5			2.00 (P)	0.58	116	89					49	Firm to stiff red CLAY (CH) - with silt traces
			2.50 (P)									
			1.25 (P)									Soft red very SILTY CLAY (CL-ML) - with sand
10			0.50 (P)									
			0.75 (P)	0.46	117	93					9	
			0.75 (P)									Very loose to loose red CLAYEY SILT (ML) - with sand
			0.50 (P)									
20			WOH				93 (g)					
			0.00 (P)									
			0.75 (P)									
5			0.00 (P)									
			WOH									
30			WOH				65					Very loose red SANDY SILT (ML) - with clay
			1.25 (P)									Very loose red CLAYEY SILT (ML) - with sand
35			WOH				80					
			0.50 (P)									
40			WOH									
												Boring Terminated at 40 Feet.
45												
50												
Groundwater Level Data				Advancement Method				Notes				
<input checked="" type="checkbox"/> First encountered at 9 ft. <input checked="" type="checkbox"/> Hole fell in at 10.5 ft. after 10 min.				Short-flight Auger: 0' - 12' Rotary Wash: 12' - 40'				g: See attached grain size curve				
				Abandonment Method								
				Hole backfilled with cement/bentonite grout upon completion.								



204.GPJ, AQUATERRA.GDT 12/05
AU LOG

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-21

SHEET 1 OF 2

FILE: 914206
DATE: Dec. 15, 2004
DRILLER: R. Warren
TECH.: J. Rummler
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

FIELD DATA			LABORATORY DATA						Location: See Figure 2. Lat. 31° 23' 21.5" Long. 92° 42' 02.3"		Strata Break Depth	Soil Type
Depth (feet)	Samples Groundwater Level	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index PI		
				Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit			
		3.50 (P)										
		1.00 (P)	0.49	112	94		17	27		10		
5		2.00 (P)										
		1.25 (P)										
10		0.75 (P)										
		WOH										
		WOH										
15		WOH										
		WOH										
20		WOH										
		6 b/f 2-3-3				49 (g)						
		2 b/f 1-1-1										
5		WOH										
		WOH										
30		WOH										
		28 b/f 5-13-15				23 (g)						
35												
40		22 b/f 6-8-14										
45		29 b/f 11-14-15										
50		15 b/f 7-8--										
STRATA BOUNDARIES MAY NOT BE EXACT												
Groundwater Level Data			Advancement Method						Notes			
First encountered at 10 ft. Hole fell in at 10 ft. after 5 min.			Short-flight Auger: 0' - 12' Rotary Wash: 12' - 100'						g: See attached grain size curves			
			Abandonment Method									
			Hole backfilled with cement/bentonite grout upon completion.									



204.GPJ, AQUATERRA.GDT 1/3/05

AQ LOG

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-21

SHEET 2 OF 2

FILE: 914206
DATE: Dec. 15, 2004
DRILLER: R. Warren
TECH.: J. Rummier
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

FIELD DATA			LABORATORY DATA						Location: See Figure 2. Lat. 31° 23' 21.5" Long. 92° 42' 02.3"		Strata Break Depth	Soil Type	
Depth (feet)	Samples Groundwater Level	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index			
				Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI	DESCRIPTION		
55	X	22 b/f 10-11--									Medium dense tan SILTY fine SAND (SM) (continued)	55.0	SAND
60	X	14 b/f 6-8--				8 (g)	20				Medium dense to dense tan and gray medium SAND (SP)	62.0	
65	X	35 b/f 14-21--									Medium dense tan and gray SILTY fine SAND (SM)	72.0	
70	X	24 b/f 8-10-14				33	22						
75		1.25 (P)	0.86	126	108		10	27	17	17	Firm gray SANDY CLAY (CL)	78.0	
80	X	23 b/f 11-12--									Medium fense light gray fine SAND (SP) - with silt	90.0	CLAY
85	X	24 b/f 12-12--											
90	X	19 b/f 8-11--				8 (g)	21				Hard gray CLAY (CH) - with silt		
95		4.50+ (P)	4.95	105	77		30	64	36	34			
100	X	50+ b/f									Boring Terminated at 100 Feet.		100.0
Groundwater Level Data			Advancement Method						Notes				
<input checked="" type="checkbox"/> First encountered at 10 ft. <input checked="" type="checkbox"/> Hole fell in at 10 ft. after 5 min.			Short-flight Auger: 0' - 12' Rotary Wash: 12' - 100'						g: See attached grain size curves				
			Abandonment Method										
			Hole backfilled with cement/bentonite grout upon completion.										

PROJECT: Geotechnical Investigation
CLECO - Rodemacher Expansion
Lena, Louisiana

SOIL BORING LOG

No. B-22

SHEET 1 OF 1

FILE: 914206
DATE: Dec. 14, 2004
DRILLER: R. Warren
TECH.: J. Rummler
ENGINEER: V. Donald

CLIENT: CLECO Corporation
Pineville, Louisiana

FIELD DATA			LABORATORY DATA						Location: See Figure 2. Lat. 31° 23' 21.5" Long. 92° 41' 57.1"		Strata Break Depth	Soil Type
Depth (feet)	Samples	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Percent Fines	Natural Moisture Content and Atterberg Limits			Plasticity Index		
	Groundwater Level			Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit	PI	DESCRIPTION	
		1.75 (P)									Stiff red and brown slightly SILTY CLAY (CL-CH)	
		1.25 (P)	1.87	122	99		19	50		31		4.0
5	X	WOH									Very loose red CLAYEY SILT (ML)	6.0
		2.25 (P)									Stiff red CLAY (CH)	
10		3.25 (P)										10.0
		3.50 (P)									Stiff red SANDY CLAY (CL)	12.0
		2.00 (P)									Firm red very SILTY CLAY (CL-ML)	
15		2.00 (P)					12	31		19		
		WOH									- very soft below 18'	
20	X	WOH				87					- with sand from 22' - 24'	
		WOH										
5	X	WOH										
		WOH										
		WOH										
30	X	WOH										
		WOH										
		WOH										
35	X	WOH									Very loose red SANDY SILT (ML)	34.0
		WOH										
		WOH				66 (g)						
40	X	WOH									Boring Terminated at 40 Feet.	40.0
45												
50												

Groundwater Level Data

First encountered at 18 ft.
No rise after 15 min.

Advancement Method

Short-flight Auger: 0' - 20'
Rotary Wash: 20' - 40'

Abandonment Method

Hole backfilled with cement/bentonite grout upon completion.


Notes

g: See attached grain size curves

STRATA BOUNDARIES MAY NOT BE EXACT



Grain Size Curves
Construction Monitoring Services
CLECO - Rodemacher Power Station
914206







Grain Size Curves

Construction Monitoring Services

CLECO - Rodemacher Power Station

914206






Grain Size Curves

Construction Monitoring Services

CLECO-Rodemacher Power Station

914206



SOIL BORING LEGEND

FIELD DATA				LABORATORY DATA				Location: Coordinate (North & East)		Soil Type																																						
Depth (feet)	Samples (Groundwater Level)	Field Test Results	Undrained Shear Strength (ksf)	Unit Weight (pcf)		Other/Percent Finer	Natural Moisture Content and Atterberg Limits				Plasticity Index	Latitude Longitude																																				
				Moist	Dry		Plastic Limit	Moisture Content	Liquid Limit																																							
										Surface Elevation: Elev.	DESCRIPTION																																					
<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p>TERMS DESCRIBING CONSISTENCY</p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2">Noncohesive Soils (includes gravels, sands and silts) Consistency determined by Standard Penetration Resistance</th> <th colspan="2">Cohesive Soils (includes clays) Consistency determined by laboratory shear strength testing or by field visual-manual procedures.</th> </tr> <tr> <th>Descriptive Term</th> <th>Standard Penetration Resistance (blows per foot)</th> <th>Descriptive Term</th> <th>Undrained Shear Strength (kips per sq. ft.)</th> </tr> </thead> <tbody> <tr> <td>Very Loose</td> <td>less than 4</td> <td>Very Soft</td> <td>less than 0.25</td> </tr> <tr> <td>Loose</td> <td>5 to 9</td> <td>Soft</td> <td>0.25 to 0.50</td> </tr> <tr> <td>Medium Dense</td> <td>10 to 29</td> <td>Firm</td> <td>0.50 to 1.00</td> </tr> <tr> <td>Dense</td> <td>30 to 50</td> <td>Stiff</td> <td>1.00 to 2.00</td> </tr> <tr> <td>Very Dense</td> <td>above 50</td> <td>Very Stiff</td> <td>2.00 to 4.00</td> </tr> <tr> <td></td> <td></td> <td>Hard</td> <td>above 4.00</td> </tr> </tbody> </table> </div> <div style="width: 45%;"> <p>FIELD TESTING</p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Standard Penetration Testing</th> <th>Pocket Penetrometer</th> </tr> </thead> <tbody> <tr> <td>The penetration resistance is the number of blows required to drive the split-spoon sampler the final 12 inches of penetration.</td> <td>Strength estimates of relatively undisturbed samples are obtained by penetrometer readings. The measured units are in tons per square foot (tsf).</td> </tr> </tbody> </table> </div> </div>											Noncohesive Soils (includes gravels, sands and silts) Consistency determined by Standard Penetration Resistance		Cohesive Soils (includes clays) Consistency determined by laboratory shear strength testing or by field visual-manual procedures.		Descriptive Term	Standard Penetration Resistance (blows per foot)	Descriptive Term	Undrained Shear Strength (kips per sq. ft.)	Very Loose	less than 4	Very Soft	less than 0.25	Loose	5 to 9	Soft	0.25 to 0.50	Medium Dense	10 to 29	Firm	0.50 to 1.00	Dense	30 to 50	Stiff	1.00 to 2.00	Very Dense	above 50	Very Stiff	2.00 to 4.00			Hard	above 4.00	Standard Penetration Testing	Pocket Penetrometer	The penetration resistance is the number of blows required to drive the split-spoon sampler the final 12 inches of penetration.	Strength estimates of relatively undisturbed samples are obtained by penetrometer readings. The measured units are in tons per square foot (tsf).	CONCRETE	
Noncohesive Soils (includes gravels, sands and silts) Consistency determined by Standard Penetration Resistance		Cohesive Soils (includes clays) Consistency determined by laboratory shear strength testing or by field visual-manual procedures.																																														
Descriptive Term	Standard Penetration Resistance (blows per foot)	Descriptive Term	Undrained Shear Strength (kips per sq. ft.)																																													
Very Loose	less than 4	Very Soft	less than 0.25																																													
Loose	5 to 9	Soft	0.25 to 0.50																																													
Medium Dense	10 to 29	Firm	0.50 to 1.00																																													
Dense	30 to 50	Stiff	1.00 to 2.00																																													
Very Dense	above 50	Very Stiff	2.00 to 4.00																																													
		Hard	above 4.00																																													
Standard Penetration Testing	Pocket Penetrometer																																															
The penetration resistance is the number of blows required to drive the split-spoon sampler the final 12 inches of penetration.	Strength estimates of relatively undisturbed samples are obtained by penetrometer readings. The measured units are in tons per square foot (tsf).																																															
											FILL																																					
5		Auger Sample									CLAY																																					
		Pocket penetrometer reading	1.00																																													
		S Shelby Tube Sample									SANDY SILT																																					
		Standard Penetration Test (blows/foot)																																														
10			35 b/f								CLAYEY SAND																																					
		Split Spoon Sample	17-17-18																																													
		No Recovery									CLAYEY SILT																																					
15											SAND																																					
		Rock Core Sample																																														
20			1.00								SILTY SAND																																					
		Probe Core Sample																																														
											SILTY CLAY																																					
											CLAYEY SILT/SILTY CLAY																																					
											SANDY CLAY																																					
											GRAVEL																																					
25																																																


STRATA BOUNDARIES MAY NOT BE EXACT

Groundwater Level Data	Advancement Method	Notes
<div style="display: flex; align-items: center;"> <div style="width: 20px; text-align: center;">▽</div> <div>Water initially encountered during dry augering</div> </div> <div style="display: flex; align-items: center;"> <div style="width: 20px; text-align: center;">●</div> <div>Groundwater level after a specified observation period</div> </div> <div style="display: flex; align-items: center;"> <div style="width: 20px; text-align: center;">▽</div> <div>Stabilized water level after an extended period of observation</div> </div> <p>Actual depth to water may vary from the conditions observed in the borings. The presence of groundwater is masked in borings advanced by rotary wash methods.</p>	<div style="border: 1px solid black; padding: 5px; margin-bottom: 5px;">Description of methodology used to advance soil boring.</div> <div style="border: 1px solid black; padding: 5px;">Abandonment Method</div> <div style="border: 1px solid black; padding: 5px;">Description of methodology used to abandon or fill the completed borehole.</div>	<div style="border: 1px solid black; padding: 5px;">Notes describing other laboratory tests or surface conditions.</div>

APPENDIX I

SOIL BORING LOGS AND MONITORING WELL CONSTRUCTION DIAGRAMS

Monitoring Well Construction Diagram Above Grade Well



**Cross-Sectional
View**

Project: Rodemacher Power Station

Project No: 01-0009

Monitoring Well: W-1

Diagram Not To Scale

L1 = 0.2 Ft

L2 = 3.3 Ft

L3 = 69.15 Ft


L4 = 10 Ft

L5 = 79.15 Ft

L6 = 0.75 Ft

CLECO

Monitoring Well Construction Diagram Above Grade Well



**Cross-Sectional
View**

Note: Maintenance activity to well - May 18, 2006

Project: Rodemacher Power Station

Project No: 01-0017

Monitoring Well: W-1 (revised)

Diagram Not To Scale

L1 = 0.2 Ft

L2 = 2.48 Ft

L3 = 49.26 Ft


L4 = 10 Ft

L5 = 59.26 Ft

L6 = 0.75 Ft

CLECO

Monitoring Well Construction Diagram Above Grade Well



Project: Rodemacher Power Station

Project No: 01-0009

Monitoring Well: W-2

Diagram Not To Scale

L1 = 0.2 Ft

L2 = 3.4 Ft


L3 = 86.2 Ft

L4 = 10 Ft

L5 = 96.2 Ft

L6 = 0.75 Ft

Monitoring Well Construction Diagram Above Grade Well



**Cross-Sectional
View**

Project: <u>Rodemacher Power Station</u> Project No: <u>01-0009</u> Monitoring Well: <u>W-3</u> Diagram Not To Scale	L1 = <u>0.2</u> Ft L2 = <u>3.3</u> Ft L3 = <u>67</u> Ft L4 = <u>10</u> Ft L5 = <u>77</u> Ft L6 = <u>0.75</u> Ft	
---	--	--

Monitoring Well Construction Diagram Above Grade Well



Project: Rodemacher Power StationProject No: 01-0009Monitoring Well: W-4

Diagram Not To Scale

L1 = 0.2 FtL2 = 2.8 FtL3 = 35.1 FtL4 = 10 FtL5 = 45.1 FtL6 = 0.75 Ft

CLECO

Monitoring Well Construction Diagram Above Grade Well



**Cross-Sectional
View**

Project: <u>Rodemacher Power Station</u> Project No: <u>01-0009</u> Monitoring Well: <u>W-5</u> Diagram Not To Scale	L1 = <u>0.2</u> Ft L2 = <u>3.3</u> Ft L3 = <u>35.1</u> Ft L4 = <u>10</u> Ft L5 = <u>45.1</u> Ft L6 = <u>0.75</u> Ft	
---	--	--

426

Monitoring Well Construction Diagram Above Grade Well


Project: Rodemacher Power StationProject No: 01-0009Monitoring Well: W-6

Diagram Not To Scale

L1 = 0.2 FtL2 = 3.0 FtL3 = 19.8 FtL4 = 10 FtL5 = 29.8 FtL6 = 0.75 Ft

Monitoring Well Construction Diagram Above Grade Well


Project: Rodemacher Power StationProject No: 01-0009Monitoring Well: W-7

Diagram Not To Scale

L1 = 0.2 FtL2 = 3.3 FtL3 = 40.3 FtL4 = 10 FtL5 = 50.3 FtL6 = 0.75 Ft

Monitoring Well Construction Diagram Above Grade Well


Project: Rodemacher Power StationProject No: 01-0009Monitoring Well: W-8

Diagram Not To Scale

L1 = 0.2 FtL2 = 2.5 FtL3 = 36.2 FtL4 = 10 FtL5 = 46.2 FtL6 = 0.75 Ft

CLECO

Monitoring Well Construction Diagram Above Grade Well


Project: Rodemacher Power StationProject No: 01-0009Monitoring Well: W-9

Diagram Not To Scale

L1 = 0.2 FtL2 = 2.75 FtL3 = 20.4 FtL4 = 10 FtL5 = 30.4 FtL6 = 0.75 Ft

Monitoring Well Construction Diagram Above Grade Well



Project: Rodemacher Power StationProject No: 01-0009Monitoring Well: W-10

Diagram Not To Scale

L1 = 0.25 FtL2 = 2.65 FtL3 = 38.2 FtL4 = 10 FtL5 = 50 FtL6 = 0.75 Ft

Monitoring Well Construction Diagram Above Grade Well



Project: Rodemacher Power Station

Project No: 01-0009

Monitoring Well: W-11

Diagram Not To Scale

L1 = 0.25 Ft

L2 = 2.9 Ft

L3 = 38.97 Ft


L4 = 10 Ft

L5 = 48.97 Ft

L6 = 0.75 Ft



Monitoring Well Construction Diagram Above Grade Well



**Cross-Sectional
View**

Project: Rodemacher Power Station

Project No: 01-0009

Monitoring Well: W-12

Diagram Not To Scale

L1 = 0.25 Ft

L2 = 2.0 Ft

L3 = 37.55 Ft

L4 = 10 Ft

L5 = 47.55 Ft

L6 = 0.75 Ft

CLECO

Monitoring Well Construction Diagram Above Grade Well


Project: Rodemacher Power StationProject No: 01-0009Monitoring Well: W-13

Diagram Not To Scale

L1 = 0.25 FtL2 = 2.65 FtL3 = 33.05 FtL4 = 10 FtL5 = 43.05 FtL6 = 0.75 Ft



SOIL BORING LOG

BORING/WELL NO.: W-10
 TOTAL DEPTH: 50 Feet
 TOP OF CASING ELEV.: 138.41 Ft NGVD
 GROUND SURFACE ELEV.: 135.8 Ft NGVD


CLIENT: Cleco Power, LLC
 PROJECT: Rodemacher Power Station
 SITE LOCATION: Boyce, Louisiana
 PROJECT NO.: 01-0009
 LOGGED BY: J. Mayeux


DRILLING CO.: EDI Environmental
 DRILLER: D. Sandoz
 METHOD OF DRILLING: DPT / HSA
 SAMPLING METHODS: DPT / Split Spoon
 DATES DRILLED: 04/12/2005

NOTES:

☒ Water level during drilling: 40.48 feet bgs
 ☒ Water level in completed well: 40.53 feet bgs

DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	CORE RECOVERY (Percent)	SAMPLE TAKEN	WELL DESCRIPTION	WELL CONSTRUCTION
-------	--------------	------	------------------	-------------------------	--------------	------------------	-------------------







SOIL BORING LOG

BORING/WELL NO.: W-11
 TOTAL DEPTH: 50 Feet
 TOP OF CASING ELEV.: 138.15 Ft NGVD
 GROUND SURFACE ELEV.: 134.2 Ft NGVD


CLIENT: Cleco Power, LLC
 PROJECT: Rodemacher Power Station
 SITE LOCATION: Boyce, Louisiana
 PROJECT NO.: 01-0009
 LOGGED BY: J. Mayeux


DRILLING CO.: EDI Environmental
 DRILLER: D. Sandoz
 METHOD OF DRILLING: DPT / HSA
 SAMPLING METHODS: DPT / Split Spoon
 DATES DRILLED: 04/13/2005

NOTES:

≡ Water level during drilling: 41.23 feet bgs
 ≡ Water level in completed well: 40.53 feet bgs

DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	CORE RECOVERY (Percent)	SAMPLE TAKEN	WELL DESCRIPTION	WELL CONSTRUCTION
-------	--------------	------	------------------	-------------------------	--------------	------------------	-------------------







SOIL BORING LOG

BORING/WELL NO.: W-12
 TOTAL DEPTH: 50 Feet
 TOP OF CASING ELEV.: 115.66 Ft NGVD
 GROUND SURFACE ELEV.: 112.7 Ft NGVD


CLIENT: Cleco Power, LLC
 PROJECT: Rodemacher Power Station
 SITE LOCATION: Boyce, Louisiana
 PROJECT NO.: 01-0009
 LOGGED BY: J. Mayeux


DRILLING CO.: EDI Environmental
 DRILLER: D. Sandoz
 METHOD OF DRILLING: DPT / HSA
 SAMPLING METHODS: DPT / Split Spoon
 DATES DRILLED: 04/15/2005

NOTES:

≡ Water level during drilling: 12.48 feet bgs
 ≡ Water level in completed well: 12.81 feet bgs

DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	CORE RECOVERY (Percent)	SAMPLE TAKEN	WELL DESCRIPTION	WELL CONSTRUCTION
-------	--------------	------	------------------	-------------------------	--------------	------------------	-------------------







SOIL BORING LOG

BORING/WELL NO.: W-13
 TOTAL DEPTH: 50 Feet
 TOP OF CASING ELEV.: 119.17 Ft NGVD
 GROUND SURFACE ELEV.: 116.6 Ft NGVD


CLIENT: Cleco Power, LLC
 PROJECT: Rodemacher Power Station
 SITE LOCATION: Boyce, Louisiana
 PROJECT NO.: 01-0009
 LOGGED BY: J. Mayeux


DRILLING CO.: EDI Environmental
 DRILLER: D. Sandoz
 METHOD OF DRILLING: DPT / HSA
 SAMPLING METHODS: DPT / Split Spoon
 DATES DRILLED: 04/18/2005

NOTES:

≡ Water level during drilling: 16.56 feet bgs
 ≡ Water level in completed well: 16.83 feet bgs

DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	CORE RECOVERY (Percent)	SAMPLE TAKEN	WELL DESCRIPTION	WELL CONSTRUCTION
-------	--------------	------	------------------	-------------------------	--------------	------------------	-------------------







SOIL BORING LOG

BORING/WELL NO.: EE-1
 TOTAL DEPTH: 75 Feet
 TOP OF CASING ELEV.: NA Ft NGVD
 GROUND SURFACE ELEV.: 90 Ft NGVD


CLIENT: Cleco Power, LLC
 PROJECT: Rodemacher Power Station
 SITE LOCATION: Boyce, Louisiana
 PROJECT NO.: 01-0009
 LOGGED BY: J. Mayeux


DRILLING CO.: EDI Environmental
 DRILLER: D. Sandoz
 METHOD OF DRILLING: DPT / HSA
 SAMPLING METHODS: DPT / Split Spoon
 DATES DRILLED: 04/13/2005

NOTES:

☒ Water level during drilling: 8.0 feet bgs

DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	CORE RECOVERY (Percent)	SAMPLE TAKEN	WELL DESCRIPTION	WELL CONSTRUCTION
-------	--------------	------	------------------	-------------------------	--------------	------------------	-------------------





APPENDIX J

GROUNDWATER FLOW EVALUATION

**Summary Table of Water Level Elevations
Cleco Power LLC Rodemacher Power Station**

Well	Top of Casing Elevation (FT NGVD)	1/19/1999			7/15/1999			1/18/2000			7/18/2000		
		Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)		
W-1	148.65	46.00	102.65	46.16	102.49	47.77	100.88	47.57	101.08				
W-2	151.80	52.37	99.43	52.36	99.44	53.22	98.58	53.47	98.33				
W-3	93.40	21.27	72.13	22.76	70.64	25.74	67.66	24.38	69.02				
W-4	94.80	20.21	74.59	21.87	72.93	26.23	68.57	23.81	70.99				
W-5	95.20	0.85	94.35	0.40	94.80	2.15	93.05	2.38	92.82				
W-6	114.20	—	—	—	—	—	—	—	—				
W-7	117.30	14.42	102.88	15.43	101.87	17.36	99.94	16.55	100.75				
W-8	117.60	15.38	102.22	16.30	101.30	18.13	99.47	17.38	100.22				
W-9	107.20	5.48	101.72	6.41	100.79	8.22	98.98	7.70	99.50				
W-10	138.41	—	—	—	—	—	—	—	—				
W-11	138.15	—	—	—	—	—	—	—	—				
W-12	115.66	—	—	—	—	—	—	—	—				
W-13	119.17	—	—	—	—	—	—	—	—				

Notes: FT = Feet

FT NGVD = Feet relative to National Geodetic Vertical Datum

**Summary Table of Water Level Elevations
Cleco Power LLC Rodemacher Power Station**

Well	Top of Casing Elevation (FT NGVD)	7/19/2001			1/14/2002			7/10/2002			7/15/2003		
		Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)
W-1	148.65	46.70	101.95	46.12	102.53	46.27	102.38	45.88	102.77	45.88	102.77		
W-2	151.80	52.75	99.05	52.22	99.58	52.20	99.60	51.93	99.87	51.93	99.87		
W-3	93.40	22.54	70.86	19.50	73.90	23.27	70.13	24.30	69.10	24.30	69.10		
W-4	94.80	20.00	74.80	17.12	77.68	21.47	73.33	22.70	72.10	22.70	72.10		
W-5	95.20	1.64	93.56	0.85	94.35	1.65	93.55	1.18	94.02	1.18	94.02		
W-6	114.20	--	--	--	--	--	--	--	--	--	--		
W-7	117.30	15.18	102.12	14.65	102.65	15.80	101.50	15.03	102.27	15.03	102.27		
W-8	117.60	16.16	101.44	15.60	102.00	16.75	100.85	15.90	101.70	15.90	101.70		
W-9	107.20	6.31	100.89	5.73	101.47	6.84	100.36	6.50	100.70	6.50	100.70		
W-10	138.41	--	--	--	--	--	--	--	--	--	--		
W-11	138.15	--	--	--	--	--	--	--	--	--	--		
W-12	115.66	--	--	--	--	--	--	--	--	--	--		
W-13	119.17	--	--	--	--	--	--	--	--	--	--		

Notes: FT = Feet


FT NGVD = Feet relative to National Geodetic Vertical Datum

**Summary Table of Water Level Elevations
Cleco Power LLC Rodemacher Power Station**

Well	Top of Casing Elevation (FT NGVD)	7/13/2004		1/18/2005		5/6/2005		5/26/2005	
		Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)	Depth -to- Water (FT)	Water Elevation (FT NGVD)
W-1	148.65	44.76	103.89	45.14	103.51	45.01	103.64	45.25	103.40
W-2	151.80	51.38	100.42	51.78	100.02	51.54	100.26	51.64	100.16
W-3	93.40	21.35	72.05	18.40	75.00	23.28	70.12	25.61	67.79
W-4	94.80	19.50	75.30	20.33	74.47	21.66	73.14	24.65	70.15
W-5	95.20	0.50	94.70	1.00	94.20	1.08	94.12	1.35	93.85
W-6	114.20	--	--	--	--	--	--	--	--
W-7	117.30	14.40	102.90	15.12	102.18	15.08	102.22	21.71	95.59
W-8	117.60	15.30	102.30	15.87	101.73	15.86	101.74	20.69	96.91
W-9	107.20	8.42	98.78	6.00	101.20	6.02	101.18	18.93	88.27
W-10	138.41	--	--	--	--	40.53	97.88	40.75	97.66
W-11	138.15	--	--	--	--	40.53	97.62	42.65	95.50
W-12	115.66	--	--	--	--	12.81	102.85	13.01	102.65
W-13	119.17	--	--	--	--	16.83	102.34	17.54	101.63

Notes: FT = Feet

FT NGVD = Feet relative to National Geodetic Vertical Datum




DECO Power LLC
Rodemacher Power Station


Groundwater Contour Map
May 6, 2005

Rapides Parish, Louisiana

Drawn:	Imp
Checked:	JHM
Approved:	RS
Date:	06/15/05
Dwg. No.:	01-0009-B003


Figure J-1






APPENDIX K


ENGINEERING DATA



PLANT DEVELOPMENT
RODEMACHER POWER STATION
UNIT 2
SOLID WASTE MANAGEMENT
PLAN PERMIT APPLICATION

EXHIBIT 7






SECTION A-A

LEGEND

- D = DEPTH IN FEET
- N = STANDARD PENETRATION TEST, BLOWS PER FOOT
- ▽ = GROUND WATER LEVEL



GENERALIZED SUBSURFACE DIAGRAM
CLARIFIER SLUDGE POND

RODEMACHER POWER STATION UNIT 2
SOLID WASTE MANAGEMENT PLAN
PERMIT APPLICATION

EXHIBIT 9

APPENDIX L

GROUNDWATER SAMPLING AND ANALYSIS PLAN

**CLECO POWER, LLC
RODEMACHER POWER STATION
BOYCE, LOUISIANA**

**FACILITY I.D. No. GD-079-0390
PERMIT NOS. P-0005, P-0027, P-0062,
AND P-0379**

**RODEMACHER POWER STATION
SOLID WASTE PERMITTED FACILITIES
GROUNDWATER
SAMPLING AND ANALYSIS PLAN**

SEPTEMBER 2006

Prepared By:

**Eagle Environmental Services, Inc.
18369 Petroleum Drive
Baton Rouge, Louisiana 70809
(225) 757-0870**

Eagle Project No. 01-0020

TABLE OF CONTENTS

<u>Section</u>	<u>Page No.</u>
1.0 INTRODUCTION.....	1
1.1 Scope of Sampling and Analysis Plan.....	1
2.0 GROUNDWATER MONITORING SYSTEM	2
2.1 Site Description.....	2
2.2 Uppermost Aquifer	2
2.3 Monitoring Well Network	2
3.0 DETECTION MONITORING PARAMETERS	3
4.0 MONITORING AND SAMPLING PROCEDURES.....	4
4.1 Groundwater Monitoring Schedule.....	4
4.2 Pre-Field Considerations	4
4.3 Well Inspection Procedures	4
4.4 Sample Collection Procedures.....	5
4.4.1 Purging and Sampling Equipment	5
4.4.2 Water Level and Total Depth Measurement Procedures.....	5
4.4.3 Well Purging Procedures.....	6
4.4.4 Sample Collection Procedures	7
4.4.5 Field Measurements	8
4.4.6 Well Maintenance/Post-Collection Procedures	9
4.4.7 Sample Preservation.....	9
4.4.8 Chain-of-Custody Control.....	9
4.4.9 Sample Shipment/Transport.....	9
5.0 QUALITY ASSURANCE/QUALITY CONTROL (QA/QC)	10
5.1 Field Quality Control.....	10
5.1.1 Field Documentation	10
5.1.2 Decontamination Procedures	11
5.1.3 Field and Equipment (Rinsate) Blanks	12
5.2 Laboratory Quality Control	12
6.0 ANALYTICAL PROCEDURES	12
7.0 GROUNDWATER DATA STATISTICAL EVALUATION	12
8.0 REPORTING AND RECORDKEEPING.....	13

LIST OF EXHIBITS

Exhibit

- 1 MONITORING WELL LOCATIONS – RELEVANT POINT OF COMPLIANCE
- 2 DETECTION MONITORING PARAMETER SPECIFICATIONS
- 3 GROUNDWATER SAMPLING DATA FORM
- 4 CHAIN-OF-CUSTODY FORM (SAMPLE)

1.0 INTRODUCTION

The purpose of this document is to detail the Groundwater Sampling and Analysis Plan designed to monitor groundwater quality in the uppermost aquifer for the Cleco Power, LLC (Cleco) Rodemacher Power Station. The Rodemacher Power Station will be conducting a detection monitoring program, as required in LAC 33:VII.521.F.5.c and e, as well as LAC 33:VII.709.E.2, 3, and 4. The Rodemacher Power Station operates four solid waste permitted facilities identified as the following:

P-0005 Unit 2 Metal Cleaning Waste Pond, Bottom Ash Pond, and Fly Ash Pond

P-0027 Unit 1 Metal Cleaning Waste Pond

P-0062 Coal Sedimentation Runoff Pond

P-0379 Ash Management Area

A site map showing the location of the permitted facilities and the associated monitoring wells is shown in Exhibit 1.

The focus of implementation of this Groundwater Sampling and Analysis Plan is to collect and sample groundwater from the uppermost aquifer underlying the permitted Solid Waste facilities for analysis of a selected list of chemical parameters, constituents which are indicator parameters or constituents, or reaction products of the waste, and would provide a reliable indication of the presence of potential contaminants in the groundwater at an early stage. This Groundwater Sampling and Analysis Plan describes the consistent sampling and analysis procedures which will be implemented to ensure that results from detection monitoring sampling events are representative of groundwater quality at the background and downgradient monitoring well locations. This Sampling and Analysis Plan also describes the procedures to detect, report, and verify changes in the groundwater quality.

1.1 Scope of Sampling and Analysis Plan

The purpose of this document is to assist in minimizing the groundwater sample collection as a source of variability through differences in sampling personnel and their individual sampling procedures. This Groundwater Sampling and Analysis Plan addresses the procedures requisite for the proper collection of consistent representative water samples from monitoring wells at the permitted Solid Waste facilities.

This plan is organized into the following sections:

- Section 2.0 describes the site facility, uppermost aquifer, and monitoring well network;
- Section 3.0 describes the detection monitoring parameters;
- Section 4.0 describes the monitoring and sampling procedures;

- Section 5.0 describes the Quality Assurance/Quality Control (QA/QC) procedures;
- Section 6.0 describes the analytical procedures;
- Section 7.0 describes the statistical analysis procedures; and
- Section 8.0 describes the reporting and recordkeeping procedures.

2.0 GROUNDWATER MONITORING SYSTEM

2.1 Site Description

The Rodemacher Power Station is located near Boyce, Louisiana, and currently operates four permitted Solid Waste facilities for the disposal of on-site-generated non-hazardous solid waste at the power station.

2.2 Uppermost Aquifer

The uppermost aquifer underlying the Rodemacher Power Station consists of deposits of fine- to coarse-grained sand deposits with some silt and gravel. The gravels are primarily located at the base of the sand unit. Monitoring wells screened in this unit indicate that groundwater flow is primarily towards the local surface water bodies such as Lake Rodemacher and Bayou Jean de Jean.

2.3 Monitoring Well Network

The proposed groundwater monitoring system for the solid waste facilities is summarized below:

P-0005	Background Well	W-1, W-2, W-22
	Compliance Wells	W-3, W-4, W-5, W-6A, W-10, W-11, W-14, W-15, W-16, W-17, W-18, W-19, W-20
P-0379	Background Well	W-2, W-22
	Compliance Wells	W-3, W-4, W-5, W-14, W-15, W-16, W-17, W-18, W-19, W-20
P-0027	Background Well	W-1, W-2
	Compliance Wells	W-8, W-9
P-0062	Background Well	W-1, W-2
	Compliance Wells	W-7, W-8, W-21

Construction details of these wells are included in Exhibit 1.

Please note that wells W-6A, W-14, W-15, W-16, W-17, W-18, W-19, W-20, W-21, and W-22 are not currently installed. Monitoring well W-6A will replace well W-6. To finalize the design of the groundwater monitoring detection system, these wells will be installed to satisfy the spacing requirements of LAC 33:VII.709.C. The location of the wells and the proposed Point of Compliance is shown in the figure included as Exhibit 1.

The proposed monitoring wells will be constructed in accordance with applicable portions of "Construction of Geotechnical Boreholes and Groundwater Monitoring Systems Handbook," [LDEQ and Louisiana Department of Transportation and Development, December 2000]. The top-of-casings will be surveyed relative to NGVD in order to use groundwater elevation from the wells to evaluate horizontal and vertical groundwater flow.

3.0 DETECTION MONITORING PARAMETERS

The parameters selected by the Rodemacher Power Station during detection monitoring are both inorganic and organic and are also indicative or reaction products of the waste disposed in the permitted Solid Waste facilities, as required by LAC 33:VII.709.E.3.g. Monitoring these parameters will provide a reliable indication of the presence of contaminants in the groundwater. The detection monitoring parameters are:

- pH (field-measured);
- Specific conductance (field-measured);
- Temperature (field-measured);
- Total dissolved solids;
- Alkalinity (mg/l as CaCO₃);
- Sulfates;
- Chlorides;
- Total calcium;
- Total copper; and
- Total iron.

These parameters were selected based on several factors, and monitoring the selected parameters will provide a reliable indication of the presence of contaminants in the groundwater underlying the permitted solid waste facilities.

Parameters specific conductance and temperature will not be used for groundwater quality evaluation in regards to statistical evaluation of groundwater quality data. The remaining parameters will provide site-specific groundwater quality data for the Rodemacher Power Station.

4.0 MONITORING AND SAMPLING PROCEDURES

4.1 Groundwater Monitoring Schedule

Initial sampling for detection monitoring will occur after receipt of LDEQ approval of this plan. Initial sampling will include a minimum of four independent samples collected from each well for analysis of the detection monitoring parameters. The minimum of four independent sampling events will be conducted to reflect seasonal variations in groundwater quality. The sampling events may be increased to a number greater than four for statistical analysis requirements. Initial sampling will be initiated following approval from LDEQ.

Sampling and analysis of the groundwater monitoring wells will be conducted every six months for the life of the facility as required by LAC 33:VII.709.E.3.c and d. LAC 33:VII.709.E.3.d also requires detection monitoring for the period of post-closure care.

4.2 Pre-Field Considerations

These procedures must be considered prior to performance of sampling activities. These considerations include but are not limited to:

- Scheduling for analytical services;
- Selecting proper analytical equipment;
- Decontamination of sampling equipment; and
- Selection and acquisition of appropriate sample containers, preservatives, and storage containers.

The facility thoroughly prepares prior to sampling events to ensure that sample collection produces representative samples of the zone monitored and to prevent cross-contamination or tampering with the samples. In preparation of any sample collection activities, a review is made to confirm that all necessary sampling equipment and supplies will be available at the sampling site. In addition, a review of the Detection Monitoring Parameter Specifications (Exhibit 2) is done to determine if any chemical preservatives are needed for the sample containers.

4.3 Well Inspection Procedures

The monitoring wells are protected by locking shrouds and covers. Each monitoring well will be inspected during each groundwater monitoring event for the following items:

1. Evidence of tampering.
2. Presence of intact locking shrouds and covers.
3. Condition of locks.
4. Condition of well pads, paint, and well labels.

Any areas of concern will be noted in the field log book and promptly corrected.

4.4 Sample Collection Procedures

This Groundwater Sampling and Analysis Plan provides for a step-by-step process to collect groundwater samples. A general overview of sampling procedures is listed in the following sections.

4.4.1 Purging and Sampling Equipment

The following list of equipment may be used for well purging and sampling:

- Dedicated or disposable hand bailer
- Hand pump with associated piping
- Positive gas displacement (bladder) pump with air supply and discharge hose
- Centrifugal lift pump and suction hose, or other comparable purging equipment
- Positive electric displacement pump with electric supply and discharge hose
- Peristaltic pump and suction hose, or other comparable purging equipment
- Portable pH meter (with calibration solutions)
- Portable conductivity meter (with calibration solutions)
- Portable temperature meter
- Ice chests (with ice)
- Groundwater collection sheets (field book)
- Chain-of-custody sheets
- Surgical laboratory gloves
- Water level indicator (accuracy 0.01 feet)
- Sample bottles from laboratory
- Sample bottle labels with waterproof pen
- Watch
- Five-gallon containers
- Deionized water
- Liqui-Nox, Alconox, or other non-phosphate detergent
- Polyethylene rope
- Clean paper towels
- Plastic sheeting

4.4.2 Water Level and Well Total Depth Measurement Procedures

Determine the static water level (DTW) in each well below the top of casing (TOC) using a water level indicator or weighted tape. Record the DTW on the field form to the nearest 0.01 foot.

Determine the total depth (TD) in each well below the top of casing (TOC) using a water level indicator or weighted tape. Record the TD on the field form to the nearest 0.01 foot.

An example groundwater collection report form is included as Exhibit 3.

4.4.3 Well Purging Procedures

The following outlines the procedures used to purge the monitoring wells.

1. Calculate the volume of water to be purged from the well (VP) using the following formula:

$$VP = 3 (TD - DTW) (\pi r^2) (c); \text{ where}$$

VP = volume to be purged (gallons)

TD = total depth of well (feet)

DTW = depth to water from top of casing (feet)

$\pi = 3.14$

r^2 = radius of well squared (feet)

c = constant, 7.481 gallons per cubic foot

Note: If the well is evacuated to dryness, no additional purging is necessary.

2. Purge wells by either withdrawal of groundwater with pumps or bailers.
 - a. If purging is performed with pumps, purge the well until the required VP has been removed or to dryness, whichever occurs first.

Record the volume removed on the Groundwater Sampling Data Form. Note any odors, colors, etc. that are observed during pumping on the field notes.

- b. If purging is performed with a bailer, rinse with liberal amounts of deionized water. After cleaning, lower the bailer into the water using clean new polyethylene rope. Bail until the required VP has been removed or to dryness, whichever occurs first. Discard the polyethylene rope when purging is completed.

Record the purge volume and time on a Groundwater Sampling Data Form. Note any odors, colors, etc. that are observed during bailing on the field notes.

Decontamination procedures for pumps, bailers and other non-dedicated equipment are included in Section 5.1.2.

4.4.4 Sample Collection Procedures

The procedures for sampling monitoring wells are outlined in the following paragraphs. The procedures are to be used after the well has been purged and sufficiently recharged to collect the required sample quantities. Sample bottles with appropriate preservatives will be furnished by an independent analytical laboratory.

Note: The designated background monitoring well(s) shall be sampled first, and then downgradient monitoring wells can be sampled.

The following procedures will be used to collect samples from the monitoring wells.

1. Put on new surgical/lab gloves for each sampling location.
2. Organize and lay out sampling equipment, bottles, and logging information.
3. Verify that labels on sample containers, groundwater collections report sheets, and chain-of-custody forms are consistent with the well number being sampled. All collection bottles shall be pre-washed by the laboratory. Water-resistant marking shall be used to label the sample bottles and the container label shall be checked for proper markings.
4. Samples will be collected using the dedicated bladder pump and associated tubing or with dedicated bailer.

If collecting via pump, use the following steps:

Carefully pour the water into the analytical sample bottles, taking care not to excessively agitate water in the sample container. No dirt or dust should be allowed to blow into the bottles or bottle caps.

If collecting via bailer, use the following steps:

Purge the well by slowly lowering the bailer into the well and allowing water to fill the bailer, retrieving the bailer, and then pouring the water into a bucket or plastic tub. The bucket or plastic tub can be used to quantify the volume of water purged from the well.

Collect samples by slowly lowering the bailer into the water, allowing it to fill. Take care to not excessively agitate water in the well with the bailer. When the bailer is full, carefully retrieve the bailer and carefully pour the water into the analytical sample bottles. Allow no dirt or dust to blow into the bottles or bottle caps.

5. Use a portion of the first sample retrieved for immediate measurement of the field parameters pH, specific conductance, and temperature. Pour water into a separate jar (see Section 4.4.5 for field measurement procedures) to determine these parameter readings. Calibrate the field instruments prior to sample collection activities, and then after completion of sampling activities. Document all calibration records in the field log book.
6. Carefully pack the samples in ice chests or coolers packed with ice or freezer packs as soon after collection as possible. To minimize possible leakage, arrange samples and ice so that the sample containers will not make contact during shipment.
7. Complete the chain-of-custody transfer record for the sample. An example chain-of-custody transfer form is included in Exhibit 4.
8. Transport the samples, with the chain-of-custody form(s), to the independent analytical laboratory. Enclose the chain-of-custody form(s) in a waterproof bag. Transport samples the same day they are collected, if possible.

Sample collection notes:

Do not overfill sample bottles with holding preservatives. While filling the bottle and once the sample is in the bottle, do not allow anything to touch the bottle opening or the sample inside. Never stick anything into the sample.

To the extent practicable, keep samples out of direct sunlight.

4.4.5 Field Measurements and Procedures

Field measurements and comments will be recorded on the Groundwater Sampling Data Form (example, Exhibit 3). Field measurements of pH, specific conductance, and temperature will be taken and recorded on the Groundwater Sampling Data Form. The instruments shall be properly calibrated, and calibration data shall be recorded in the field log book. Calibrations shall be done in accordance with the manufacturer's recommendations. If any procedures are not performed as prescribed by

the manufacturer, the reason must be stated on the field notes. The appearance of the water purged from the well will also be noted.

4.4.6 Well Maintenance/Post-Collection Procedures

If excessive silt is detected in the base of a monitoring well, the well shall be redeveloped prior to the next sampling event.

Following completion of field activities, the following will be performed:

1. Relock all monitoring well locks.
2. Thoroughly clean all field equipment.
3. Report broken or damaged equipment.

4.4.7 Sample Preservation

Samples collected will be immediately preserved in the field by placing them in an insulated ice chest containing ice and chilling them to temperatures at or below 4 degrees centigrade. Sample bottles provided by an independent analytical laboratory shall be prepared with the proper preservatives, if preservatives are necessary for the analyte.

4.4.8 Chain-of-Custody Control

Custody of groundwater samples will be documented by completing a chain-of-custody record after sample collection. The chain-of-custody is a legal document and will accompany the collected groundwater samples from the time of collection until analysis is complete and the analytical report is issued. The original chain-of-custody form shall accompany the samples through independent analytical laboratory analysis, with copies retained at any intermediate step. A member of the sampling team must be the first signature relinquishing the samples on the chain-of custody form. All persons receiving or relinquishing possession of the samples must sign the form. Duplicated and QA/QC samples shall be identified on the chain-of-custody form in order to provide proper identification to the laboratory. A sample chain-of-custody form is included in Exhibit 4.

Upon completion of the analysis, the analytical laboratory shall complete the Chain-of-Custody Form, file a copy, and send a copy to the appropriate facility representative along with the analytical results.

4.4.9 Sample Shipment/Transport

Prior to shipment, the following will be checked.

1. Sample bottles will be double-checked for leaks, cracks, proper labeling, and sufficient preservative (ice).
2. The chain-of-custody will be completed accurately. The samples shall be logged by the sampler on the Chain-of-Custody Form and the samples will be transported, with as few transfers as possible, immediately to the independent analytical laboratory. The laboratory will be notified that the samples will be arriving.
3. If direct delivery is done by field personnel of the samples to the laboratory, the samples shall be rechecked for breakage or leakage that may have occurred during transport.
4. Samples will then be signed over to laboratory personnel according to chain-of-custody procedures. No samples will be accepted that are not properly labeled and sealed. Upon receipt, the authorized laboratory personnel will store and/or prepare the samples for analysis, taking into consideration sample holding times for the parameters for which the sample will be analyzed.

5.0 QUALITY ASSURANCE/QUALITY CONTROL (QA/QC)

5.1 Field Quality Control

Field quality control measures, as described earlier in this document, are proven procedures for collecting representative samples, calibrating field testing equipment, preserving samples for analysis, and documenting chain-of-custody. These QA/QC measures contribute to sampling events' producing monitoring results that are reliable indications of groundwater quality.

5.1.1 Field Documentation

Field activities will be controlled by adherence to procedural requirements referred to in this plan, and documented primarily thorough use of a daily log for recording field activities. Pre-printed forms may be used as an aid to ensure complete data recovery and for data reduction in the office. Documentation will include the following:

- calibration check information;
- field measurement data, including water level and well-purging measurements;
- field activity notebooks;
- sample labels; and
- chain-of custody forms.

5.1.2 Decontamination Procedures

Portable and non-dedicated sampling equipment must be decontaminated to minimize cross contamination between samples. Equipment including pumps, weighted tape measures, water-level indicator tapes, and bailers will be decontaminated and protected from ambient contamination following each use. Equipment decontamination will be performed in an area relatively free of ambient organic vapors and dust.

Miscellaneous flow measurement and sampling equipment shall be washed with laboratory detergent, rinsed with deionized water, and dried before being stored.

Field instrumentation such as pH meter probes and conductivity probes should be rinsed with deionized water before storage.

General Decontamination Procedure

1. Rinse/wash wetted parts of equipment that may enter the groundwater with deionized water. If necessary, a non-phosphate detergent such as Alconox or Liqui-Nox may be used during this rinse.
2. Allow equipment to air dry.
3. Wrap with clean protective material unless equipment is to be used again immediately.

After decontamination, field equipment and sample containers shall be stored in a contaminant-free environment after being cleaned using the procedures outlined in this document.

Non-Dedicated Submersible Pumps and Hoses

1. Pump a sufficient amount of soapy water through the hose to flush out any residual purge water.
2. Using a brush, scrub the exterior of the contaminated hose and pump with soapy water. Rinse the soap from the outside of the hose with tap water. Next rinse the hose with deionized water and recoil onto the spool.
3. Pump a sufficient amount of water through the hose to flush out soapy water.
4. Pump a sufficient amount of deionized water through the hose to flush out the tap water, then purge with the pump in reverse mode, if applicable.

5. Rinse the outside of the pump and hose with deionized water (approximately 1/4 gallon).
6. Equipment will be wrapped to prevent contamination during storage or transit.

5.1.3 Field and Equipment (Rinsate) Blanks

In the event non-dedicated sampling equipment is used, then field and equipment (rinsate) blanks shall be collected in the field to detect and quantify potential chemical artifacts originating from sampling activities. The field blank is produced in the field by pouring analyte-free water into the appropriate sample containers. The equipment (rinsate) blank is produced in the field by rinsing the sampling equipment with analyte-free water and collecting the rinsate in appropriate sample containers. These blanks are subjected to the same laboratory analysis as the samples. The concentration levels of any contaminant found in the blanks will be noted and compared to sample results.

5.2 Laboratory Quality Control

The Rodemacher Power Station will submit the groundwater samples to a qualified independent laboratory that performs testing according to documented and approved procedures by trained personnel using calibrated equipment. QA/QC procedures, including field blanks, laboratory spikes and blanks, precision accuracy of analyses, and detection limits will conform to those specified in U.S. EPA *Test Methods for Evaluating Solid Waste* (SW-846).

6.0 ANALYTICAL PROCEDURES

Groundwater monitoring samples are analyzed using laboratory methods which conform to test methods outlined in the most recent approved editions of U.S. EPA *Test Methods for Evaluating Solid Waste* (SW-846), *Methods for Chemical Analysis of Water and Wastes* (EPA-600/4-79-020), or *Standard Methods for the Examination of Water and Wastewater*. The test method, method detection limit, and practical quantitation limit for each parameter monitored are provided in Exhibit 2 (Detection Monitoring Parameter Specifications).

7.0 GROUNDWATER DATA STATISTICAL EVALUATION

The statistical method(s) proposed by the facility for evaluation of groundwater quality data will be submitted to LDEQ as a permit modification within 90 days after completion of initial sampling event, in accordance with LAC 33:VII.521.F.5.e. and LAC 33.VII.709.E.2.e.

8.0 REPORTING AND RECORDKEEPING


Within 90 days after completion of field activities for each detection monitoring sampling event, the Rodemacher Power Station will submit the required number of reports to LDEQ that includes:

- Analytical results of groundwater samples;
- Documentation of the chain-of-custody of sampling and analyses;
- A scaled potentiometric surface map showing monitoring well locations, groundwater elevations with respect to mean sea level or equivalent for the stratum monitored;
- An isopleth map for each monitoring well of all detection monitoring parameters, or plots of each monitoring well by concentration of parameters versus time; and
- A statement of whether a statistically significant difference in concentration over background concentrations is detected.

The Rodemacher Power Station will maintain on site copies of each report for the life of the facility, as well as the duration of the post-closure care period, as required in LAC 33:VII.711.C.1.b.

EXHIBIT 1

MONITORING WELL LOCATIONS – RELEVANT POINT OF COMPLIANCE



CLECO Power LLC

Rodemacher Power Station

Relevant Point of Compliance

Rapides Parish, Louisiana



Drawn:	Imp
Checked:	JHM
Approved:	RS
Date:	06/26/05
Dwg. No.:	01-0009-B004

Exhibit 1

SUMMARY OF GROUNDWATER MONITORING SYSTEMS CLECO RODEMACHER POWER STATION

P-0005 = Unit 2 Metal Cleaning Waste Pond, Bottom Ash Pond, Fly Ash Pond

Background W-1, W-2, W-22 (proposed)

Compliance W-3, W-4, W-5, W-6A (proposed), W-10, W-11, W-14 (proposed),
W-15 (proposed), W-16 (proposed), W-17 (proposed), W-18
(proposed), W-19 (proposed), W-20 (proposed)

P-0379 = Ash Management Area

Background W-2, W-22 (proposed)

Compliance W-3, W-4, W-5, W-14 (proposed), W-15 (proposed), W-16
(proposed), W-17 (proposed), W-18 (proposed), W-19
(proposed), W-20 (proposed)

P-0027 = Unit 1 Metal Cleaning Waste Pond

Background W-1, W-2

Compliance W-8, W-9

P-0062 = Coal Sedimentation Pond

Background W-1, W-2

Compliance W-7, W-8, W-21 (proposed)

WELL CONSTRUCTION DATA CLECO RODEMACHER POWER STATION

Well Number	W-1	W-2	W-3	W-4	W-5
Existing or Proposed	Existing	Existing	Existing	Existing	Existing
Monitoring Well (MW) or Piezometer (P)	MW	MW	MW	MW	MW
Background (B) or Compliance (C)	B	B	C	C	C
Facility Monitored	P-0001 P-0027, P-0062	P-0001 P-0027, P-0062, P-0379	P-0005, P-0379	P-0005, P-0379	P-0005, P-0379
Casing Elevation (feet msl)	148.65	151.80	93.40	94.80	95.20
Well Depth (feet bgs)	79.15	96.20	77.00	45.10	42.60
Screen Length (feet)	10	10	10	10	10
Screened Interval (from ___ feet msl)	79.5	68.8	25.7	60.1	62.3
(to ___ feet msl)	69.5	58.8	15.7	50.1	52.3
Screen Slot Size (inches)	0.010	0.010	0.010	0.010	0.010
Casing Diameter (inches) & Material	2" PVC	2" PVC	2" PVC	2" PVC	2" PVC
Type of Grout	C/B	C/B	C/B	C/B	C/B

Well Number	W-6 A	W-7	W-8	W-9	W-10
Existing or Proposed	Proposed	Existing	Existing	Existing	Existing
Monitoring Well (MW) or Piezometer (P)	MW	MW	P	P	P
Background (B) or Compliance (C)	C	C	--	--	--
Facility Monitored	P-0005	P-0062	P-0027	P-0027	P-0005
Casing Elevation (feet msl)	TBD	117.30	117.60	107.20	138.41
Well Depth (feet bgs)	TBD	50.30	46.20	30.40	48.20
Screen Length (feet)	10	10	10	10	10
Screened Interval (from ___ feet MSL)	TBD	76.4	84.2	86.8	100.21
(to ___ feet MSL)	TBD	66.4	74.2	76.8	90.21
Screen Slot Size (inches)	0.010	0.010	0.010	0.010	0.010
Casing Diameter (inches) & Material	2" PVC	2" PVC	2" PVC	2" PVC	2" PVC
Type of Grout	C/B	C/B	C/B	C/B	C/B

Abbreviations:

P-0005 = Unit 2 Metal Cleaning Waste Pond, Bottom Ash Pond, Fly Ash Pond

P-0027 = Unit 1 Metal Cleaning Waste Pond

P-0062 = Coal Sedimentation Pond

-- = not applicable

TBD = to be determined

~ = estimated dimension

MSL = mean sea level

bgs = below ground surface

PVC = polyvinyl chloride

C/B = cement/bentonite

WELL CONSTRUCTION DATA **CLECO RODEMACHER POWER STATION**

Well Number	W-11	W-12	W-13	W-14	W-15
Existing or Proposed	Existing	Existing	Existing	Proposed	Proposed
Monitoring Well (MW) or Piezometer (P)	P	P	P	MW	MW
Background (B) or Compliance (C)	C	C	--	C	C
Facility Monitored	P-0005	--	--	P-0005	P-0005, P-0379
Casing Elevation (feet msl)	138.15	115.66	119.17	TBD	TBD
Well Depth (feet bgs)	48.97	47.56	33.05	TBD	TBD
Screen Length (feet)	10	10	10	10	10
Screened Interval (from feet msl)	99.18	78.11	86.12	TBD	TBD
(to feet msl)	89.18	68.11	76.12	TBD	TBD
Screen Slot Size (inches)	0.010	0.010	0.010	0.010	0.010
Casing Diameter (inches) & Material	2" PVC	2" PVC	2" PVC	2" PVC	2" PVC
Type of Grout	C/B	C/B	C/B	C/B	C/B

Well Number	W-16	W-17	W-18	W-19	W-20
Existing or Proposed	Proposed	Proposed	Proposed	Proposed	Proposed
Monitoring Well (MW) or Piezometer (P)	MW	MW	MW	MW	MW
Background (B) or Compliance (C)	C	C	C	C	C
Facility Monitored	P-0005, P-0379	P-0005, P-0379	P-0005, P-0379	P-0005, P-0379	P-0005
Casing Elevation (feet msl)	TBD	TBD	TBD	TBD	TBD
Well Depth (feet bgs)	TBD	TBD	TBD	TBD	TBD
Screen Length (feet)	10	10	10	10	10
Screened Interval (from feet MSL)	TBD	TBD	TBD	TBD	TBD
(to feet MSL)	TBD	TBD	TBD	TBD	TBD
Screen Slot Size (inches)	0.010	0.010	0.010	0.010	0.010
Casing Diameter (inches) & Material	2" PVC	2" PVC	2" PVC	2" PVC	2" PVC
Type of Grout	C/B	C/B	C/B	C/B	C/B

Abbreviations:

P-0005 = Unit 2 Metal Cleaning Waste Pond, Bottom Ash Pond, Fly Ash Pond

P-0027 = Unit 1 Metal Cleaning Waste Pond

P-0062 = Coal Sedimentation Pond

-- = not applicable

TBD = to be determined

~ = estimated dimension

MSL = mean sea level

bgs = below ground surface

PVC = polyvinyl chloride

C/B = cement/bentonite

WELL CONSTRUCTION DATA **CLECO RODEMACHER POWER STATION**

Well Number	W-21	W-22
Existing or Proposed	Proposed	Proposed
Monitoring Well (MW) or Piezometer (P)	MW	MW
Background (B) or Compliance (C)	C	B
Facility Monitored	P-0062	P-0005, P-0379
Casing Elevation (feet msl)	TBD	TBD
Well Depth (feet bgs)	TBD	TBD
Screen Length (feet)	10	10
Screened Interval (from ___ feet msl)	TBD	TBD
(to ___ feet msl)	TBD	TBD
Screen Slot Size (inches)	0.010	0.010
Casing Diameter (inches) & Material	2" PVC	2" PVC
Type of Grout	C/B	C/B

Abbreviations:

P-0005 = Unit 2 Metal Cleaning Waste Pond, Bottom Ash Pond, Fly Ash Pond

P-0027 = Unit 1 Metal Cleaning Waste Pond

P-0062 = Coal Sedimentation Pond

-- = not applicable

TBD = to be determined

~ = estimated dimension

MSL = mean sea level

bgs = below ground surface

PVC = polyvinyl chloride

C/B = cement/bentonite

EXHIBIT 2

DETECTION MONITORING PARAMETER SPECIFICATIONS

DETECTION MONITORING PARAMETER SPECIFICATIONS **CLECO RODEMACHER POWER STATION**

PARAMETER	FACILITY	CONTAINER	PRESERVATION METHOD	MAXIMUM HOLDING TIME	ANALYTICAL METHOD	PRACTICAL QUANTIFICATION LIMIT
pH	P-0005, P-0027, P-0062, P-0379	P, G	NA	Immediate	Field Measurement	0.1 standard unit
Specific Conductance	P-0005, P-0027, P-0062, P-0379	P, G	NA	Immediate	Field Measurement	1 micromhos/centimeter
Temperature	P-0005, P-0027, P-0062, P-0379	P, G	NA	Immediate	Field Measurement	0.1 degrees Celsius
Total Dissolved Solids	P-0005, P-0027, P-0062, P-0379	P, G	Cool to 4°C	7 days	2540 (SM), 160.1 (MCA)	10 parts per million
Alkalinity	P-0005, P-0027, P-0062, P-0379	P, G	Cool to 4°C	14 days	2320B (SM), 310.1 (MCA)	2 parts per million
Sulfates	P-0005, P-0027, P-0062, P-0379	P, G	Cool to 4°C	28 days	4500 (SM), 300.0 (MCA)	1 parts per million
Chlorides	P-0005, P-0027, P-0062, P-0379	P, G	Cool to 4°C	28 days	4500 (SM), 300.0 (MCA)	1 parts per million
Calcium	P-0005, P-0027, P-0062, P-0379	P, G	HNO ₃ to pH < 2	6 months	3500 (SM), 200.7 (MCA), 6010 (SW-846)	80 micrograms/Liter
Copper	P-0005, P-0027, P-0062, P-0379	P, G	HNO ₃ to pH < 2	6 months	3500 (SM), 200.7 (MCA), 6010 (SW-846)	5 micrograms/Liter
Iron	P-0005, P-0027, P-0062, P-0379	P, G	HNO ₃ to pH < 2	6 months	3500 (SM), 200.7 (MCA), 6010 (SW-846)	10 micrograms/Liter

Abbreviations:

P-0005 = Unit 2 Metal Cleaning Waste Pond, Bottom Ash Pond, Fly Ash Pond
P-0027 = Unit 1 Metal Cleaning Waste Pond
P-0062 = Coal Sedimentation Pond
P-0379 = Ash Management Area
P, G = plastic or glass
SM = Standard Methods for the Examination of Water and Wastewater
MCA = Methods for Chemical Analysis of Water and Wastes, EPA-600/4-79-020
SW-846 = Test Methods for Evaluating Solid Waste

EXHIBIT 3

GROUNDWATER SAMPLING DATA FORM

CLECO POWER LLC GROUNDWATER SAMPLING LOG

Client Name:	Cleco Power LLC	Site Name:	Rodemacher Power Station
Well Name:		Location:	Boyce, LA

Notes:

PURGING DATA

Total Well Depth	Depth to Water	Well Diameter / Capacity	Height of Water Column
(Total Depth - Depth to Water) x Well Capacity = 1 Well Volume =			3 Well Volumes =
Top of Casing Elevation	Depth to Water	Water Elevation	
(Well Elevation - Depth to Water) = Water Elevation			
Purge Initiated	Purge Ended	Total Purged	

FIELD MEASUREMENTS

TIME				
VOLUME PURGED (GAL)				
CUMUL VOLUME PURGED (GAL)				
PURGE RATE (GPM)				
TEMPERATURE (Degrees C)				
SPECIFIC CONDUCTANCE (µmhos/S)				
pH (s.u.)				
APPEARANCE				
ODOR				

Weather:

SAMPLING DATA

SAMPLING DATE	SAMPLE TIME	SAMPLE METHOD
SAMPLE DEVICE	COMPOSITION OF DEVICE	
SAMPLED BY / AFFILIATION	LABORATORY ANALYSES BY	

PARAMETERS

ANALYSIS	FILTERED	QUANTITY	TYPE	SIZE	PRESERVATIVE

EXHIBIT 4

CHAIN-OF-CUSTODY FORM (SAMPLE)

APPENDIX M

CLOSURE PLAN

**Closure Plan for Unit 1 Metal Cleaning Waste Pond
Cleco Power, LLC
Rodemacher Power Station**

J. Facility Closure. Standards governing facility closure are contained in LAC 33:VII.711.E (Type I and II landfills), LAC 33:VII.713.E (Type I and II surface impoundments), LAC 33:VII.715.E (Type I and II landfarms), LAC 33:VII.717.I (Type I-A and II-A facilities), LAC 33:VII.721.D (construction and demolition debris and woodwaste landfills), LAC 33:VII.723.D (Type III composting facilities), and LAC 33:VII.725.D (Type III separation facilities)

1. The closure plan for all facilities must include the following:

a. the date of final closure;

It is anticipated that Cleco site operations will continue into the foreseeable future, the life of the surface impoundments is estimated for this closure plan to be at least 15 years.

If the quantity of sludge generated in the surface impoundment interferes with the required operating depth and freeboard level, then the sludge will be excavated and placed in the Fly Ash Pond (P-0005). This measure will ensure that the surface impoundment will be able to operate for the entire life span. Therefore, the estimated date of proposed closure of the solid waste facilities is 2020.

b. the method to be used and steps necessary for closing the facility; and

The following procedure is the planned course of action to close the facility:

- 1) Portable pumps will be used to transfer residual wastewater from the Unit 1 Metal Cleaning Waste Pond.
- 2) After the free liquids are removed from the facility, the liquids in the Unit 1 Metal Cleaning Waste Pond will be discharged through Outfall 601 or 111 of LPDES Permit No. LA0008063
- 3) The solid material or sediment will be excavated and then placed on the Fly Ash Pond (P-0005). The sludges in the pond are distinguishable by color, and a visual inspection will determine when all the sludges are removed. The excavated area will then be regraded and seeded to prevent erosion. After clean closure, the Unit 1 Metal Cleaning Waste Pond will no longer be a waste disposal facility.
- 4) The excavated areas of the surface impoundment will be divided into sections based on sampling protocol in the most recent version of SW-846 and a sample from each section will be analyzed and compared to the background soil sample to determine if any contamination exists. Background soil samples will be taken at a site on the facility that has not been impacted by facility operations. If the results of the soil sample in the excavated area are approximately equal to or less than the background for copper, then it will be assumed that all solid waste has been removed.
- 5) If any of the confirmatory analyses indicate that the indicator parameter is significantly higher than the background values, then further excavation and sampling in the area(s) with the high values (hot spots) may be

**Closure Plan for Unit 1 Metal Cleaning Waste Pond
Cleco Power, LLC
Rodemacher Power Station**

required. This procedure will continue until the analytical results are reasonably comparable to the confirmatory values.

- 6) After confirmatory analytical results indicate that the former surface impoundments are clean, the LDEQ will be notified of completion of all elements of the closure operation and a final inspection will be requested.
- 7) The groundwater monitoring wells installed to detect leakage from the facilities will be plugged and abandoned in accordance with applicable requirements of the "Construction of Geotechnical Boreholes and Groundwater Monitoring Systems Handbook," December 2000, developed by the LDEQ and Louisiana Department of Transportation and Development or most recent update.
- 8) Following the clean closure notification, the levees of the surface impoundment will be leveled to original grade and seeded with a suitable grass species and fertilized to control erosion.
- 9) Equipment associated with the facility will be cleaned and salvaged for reuse.

A Quality Assurance/Quality Control (QA/QC) Procedure has been established to minimize potential sources of contamination during the sampling of the underlying soil at the facility and includes the following key elements:

- The sampling equipment will be thoroughly cleaned before sampling and between sampling locations with biodegradable soap and a stiff bottle brush, as needed, followed by rinsing with distilled water.
- Field sampling personnel will wear plastic disposable gloves at all times during sampling and will change gloves between collecting each sample to minimize the potential for cross-contamination.
- Field sampling personnel will complete a Daily Field Log on each day of the sampling operation for documentation purposes of events that may effect the quality of the analytical results. Items to be included on the daily log include description of daily activities, weather conditions, changes in sampling procedure, and other pertinent information.
- Soil samples will be placed in pre-cleaned glass jars.
- Sample containers will be labeled with a unique sample identification number, date, sampler's initials, and parameters for analyses.
- Standard chain-of-custody forms will accompany all samples to a licensed qualified analytical lab. A general practice of minimal transfers of sample bottles and recordkeeping will provide adequate chain-of-custody control.
- The field personnel are responsible for the custody and care of collected samples until the containers have been transferred to the laboratory. The field sampler and laboratory custodian sign the Chain-of-Custody form. The field sampler retains a copy of the form and the laboratory keeps the original form.
- Sampling holding times will be minimized and shall not exceed those listed in EPA SW-846.
- Analytical procedures will be in accordance with EPA SW-846.

**Closure Plan for Unit 1 Metal Cleaning Waste Pond
Cleco Power, LLC
Rodemacher Power Station**

- c. the estimated cost of closure of the facility, based on the cost of hiring a third party to close the facility at the point in the facility's operating life when the extent and manner of its operation would make closure the most expensive.

The estimated cost of closure of the Unit 1 Metal Cleaning Waste Pond in 2005 dollars is \$74,000 as detailed in the following table.

OPERATION	CALCULATION	ESTIMATED COST*
Mobilization/Demobilization	Lump sum	\$20,000
Dewater surface impoundment	Approx. 100,000 gallons, pumped at rate of 3,000 gpd, \$650 per day per pump	\$21,500
Dispose remaining sludges in Fly Ash Pond	Approx. 1,000 yd ³ @ \$6.00/yd	\$6,000
Sampling and Testing	\$16,500	\$16,500
Certification Package	\$5,000	\$5,000
Regrade/Level	50 hours @ \$100.00/hour	\$5,000
TOTAL		\$74,000

* = In 2005 dollars.

Cleco will notify the administrative authority within 15 days of any adjusted cost estimate in the event a change in closure plans occurs, and within 30 days after each anniversary of the date on which the first cost estimate was prepared on the basis of the *Consumer Price Index Inflation Calculator* or a re-estimation of the closure and post-closure costs in accordance with LAC 33:VII.727.A.2.b.i and ii. Cleco will revise the cost estimate whenever a change in the closure/post-closure plans increases or decreases the cost of the closure.

2. The closure plan for Type I and II landfills and surface impoundments must include:

- a. a description of the final cover and the methods and procedures used to install the cover;

Cleco intends to remove all solid waste and contaminated soil within the Unit 1 Metal Cleaning Waste Pond to obtain a clean closure. As part of the clean closure, the site will be graded to the original ground elevation and seeded and fertilized to allow for vegetative growth to prevent erosion.

- b. an estimate of the largest area of the facility ever requiring a final cover at any time during the active life;

**Closure Plan for Unit 1 Metal Cleaning Waste Pond
Cleco Power, LLC
Rodemacher Power Station**

The Unit 1 Metal Cleaning Waste Pond will be clean-closed and will not require final cover.

- c. **an estimate of the maximum inventory of solid waste ever on-site over the active life of the facility; and**

The maximum volume of solid waste within the Unit 1 Metal Cleaning Waste Pond is estimated to be approximately 9,000 cubic yards.

- d. **a schedule for completing all activities necessary for closure.**

The Closure Schedule below lists the activities necessary to complete closure and the estimated amount of time required to complete these tasks.

OPERATION	LENGTH (days)	ACCUMULATED TIME (days)
Set Up and Mobilize	2	2
Dewater Pond	20	22
Remove/Apply Sludges to Fly Ash Pond	20	42
Sampling Event	7	49
Submit Samples to Laboratory for Analysis	28	77
Review Analytical Data	3	80
Submit Confirmatory Results to LDEQ Obtain Clean Closure Approval from LDEQ	28	108
Abandon Monitoring Wells	5	113
Grade to Original Ground Level	50	163
Seed and Fertilize	14	177
Clean Up and Demobilize	7	184

As previously stated, it is anticipated that the surface impoundments will continue to operate until at least 2020. Prior to closure, LDEQ will be notified in writing at least 90 days prior to the anticipated start of closure.

3. **The closure plan for all Type I and II facilities and Type III woodwaste and construction/demolition debris facilities shall include the following:**

- a. **the sequence of final closure of each unit of the facility, as applicable;**

The sequence of final closure of each unit of the facility is listed in the response given for LAC 33:VII.521.J.2.d.

- b. **a drawing showing final contours of the facility; and**

As a result of clean closure, the site will be returned to its original condition and contours. The Area Master Plan depicts the contours for the Cleco RPS site.

**Closure Plan for Unit 1 Metal Cleaning Waste Pond
Cleco Power, LLC
Rodemacher Power Station**

- c. a copy of the document that will be filed upon closure of the facility with the official parish recordkeeper indicating the location and use of the property for solid waste disposal, unless the closure plan specifies a clean closure.

Cleco's closure plan provides for a clean closure for the Unit 1 Metal Cleaning Waste Pond, but if background constituent levels cannot be met, a request for an alternate closure will be made to demonstrate that the removed material is below the level based on indicator parameters in the soil. If it can be shown that this level will be adequately protective of human health and the environment (including groundwater), then a request will be made that the LDEQ decrease or eliminate the post-closure period. Within 90 days after such a closure is completed, a mortgage and conveyance records document will be entered to the parish for the property, a notation stating that solid waste remains at the site and providing the indicator levels obtained during closure.

Cleco understands that the LDEQ will release the closure fund to them upon determination that the facility has completed closure in accordance with the approved plan.

- K. **Facility Post-closure. Standards governing post-closure requirements are contained in LAC 33:VII.711.F (Type I and II landfills), LAC 33:VII.713.F (Type I and II surface impoundments), LAC 33:VII.715.F (Type I and II landfarms), and LAC 33:VII.721.E (Type III construction and demolition debris and woodwaste landfills).**

Cleco acknowledges the regulations of this subsection. Cleco will not be governed by post-closure standards after a clean closure determination has been reached by the LDEQ, as stated in LAC 33:VII.713.E.3.b. Therefore, LAC 33:VII.521.K is not applicable.

APPENDIX N

FINANCIAL ASSURANCE AND ANNUAL REPORT

Jun. 30. 2005 9:34AM CLECO PGO 6 FAX

No. 6339 P. 1

Cleco Power LLC

A subsidiary of Cleco Corporation
PO Box 5000
Pineville, LA 71361-5000
www.cleco.com

March 30, 2005

Office of the Secretary
Louisiana Department of Environmental Quality
P. O. Box 4312
Baton Rouge, LA 70821-4312

SUBJECT: Demonstration of Financial Responsibility Fiscal Year 2004

Gentlemen:

I am the chief financial officer of Cleco Power LLC (Cleco Power), 2030 Donahue Ferry Road, Pineville, Louisiana 71360. This letter is in support of this firm's use of the financial test to demonstrate financial responsibility for liability coverage and closure and post-closure care, as specified in LAC 33:VII.727.A.1 and A.2.

The firm identified above is the permit holder of the following solid waste facilities, whether in Louisiana or not, for which liability coverage is being demonstrated through the financial test specified in LAC 33:VII.727.A.1. The amount of annual aggregate liability coverage covered by the test is shown for each facility:

Dolet Hills Power Station, Site Identification Number GD-031-1551; \$1,000,000

Surge and Auxiliary Surge Ponds	P-0038
Metal Cleaning Waste Pond	P-0039
Bottom Ash Disposal Pond	P-0037
Plant Discharge Collection Pond	P-0040
Lignite Pile Runoff Pond	P-0041
Fly Ash/Scrubber Sludge Landfill and Surface Impoundment	P-0064

06/30/2005 09:55AM

Jun.30. 2005 9:35AM CLECO PGO 6 FAX

No.6339 P. 2

Rodemacher Power Station, Site Identification Number GD-079-0390; \$1,000,000

Coal Sedimentation Pond	P-0062
Unit 2 Boiler Waste Cleaning Pond	P-005
Bottom Ash Pond	P-005
Fly Ash Pond	P-005
Metal Cleaning Waste Pond	P-0027

The firm identified above is the permit holder of the following solid waste facilities, whether in Louisiana or not, for which financial assurance for closure and post-closure is demonstrated through a financial test similar to that specified in LAC 33:VII.727.A.2 or other forms of self-insurance. The current closure and post-closure cost estimates covered by the test are shown for each facility:

Dolet Hills Power Station, Site Identification Number GD-031-1551

Facility Name	Closure Cost	Post-Closure Cost
Surge and Auxiliary Surge Ponds	\$ 179,762	\$ -0-
Metal Cleaning Waste Pond	\$ 179,672	\$ -0-
Bottom Ash Disposal Pond	\$1,626,260	\$215,715
Plant Discharge Collection Pond	\$ 143,809	\$ -0-
Lignite Pile Runoff Pond	\$ 74,302	\$ -0-
Fly Ash/Scrubber Sludge Landfill and Impoundment	\$1,381,422	\$179,762

Rodemacher Power Station, Site Identification Number GD-079-0390

Facility Name	Closure Cost	Post-Closure Cost
Coal Sedimentation Pond	\$ 239,684	\$ -0-
Unit 2 Boiler Cleaning Waste Pond	\$ 107,859	\$ -0-
Bottom Ash Pond	\$1,006,675	\$107,859
Fly Ash Pond	\$2,756,373	\$151,002
Unit 1 Metal Cleaning Waste Pond	\$ 29,959	\$ -0-

This firm guarantees through a corporate guarantee similar to that specified in LAC 33:VII.727.A.1 and 2, liability coverage, closure and post-closure care of the following solid waste facilities, whether in Louisiana or not, of which Cleco Power is a subsidiary of this firm. The amount of annual liability coverage covered by this guarantee for each facility and/or the current cost estimates for the closure and/or post-closure care so guaranteed is shown for each facility:

NONE

06/30/2005 09:55AM

Jun. 30. 2005 9:35AM CLECO PGO 6 FAX

No. 6339 P. 3

This firm is the owner or operator of the following solid waste facilities, whether in Louisiana or not, for which financial assurance for liability coverage, closure and/or post-closure care is not demonstrated either to the U. S. Environmental Protection Agency or to a State through a financial test or any other financial assurance mechanism similar to those specified in LAC 33:VII.727.A.1 and /or 2. The current closure and/or post-closure cost estimates not covered by such financial assurance are shown for each facility:

NONE

This firm is required to file a Form 10K with the Securities and Exchange Commission (SEC) for the latest fiscal year.

The fiscal year of this firm ends on December 31. The figures for the following items marked with an asterisk are derived from this firm's independently audited, year-end financial statements for the latest completed year, ended December 31, 2003.

1.	Sum of current closure and post-closure cost estimates:	\$ 8,380,201
2	Amount of annual aggregate liability coverage to be demonstrated:	\$ 2,000,000
3.	Sum of lines 1 and 2:	\$ 10,380,201
4.	Current bond rating of most recent issuance and name of rating service:**	Moody A ₃ S&P BBB+
5.	Date of issuance of bond:	March 15, 1990
6.	Date of maturity of bond:**	March 15, 2005

**Both Moody's Investor Services and Standard & Poors continue to provide a secured debt rating on this firm even though no bonds have recently been issued. The ratings shown above are the ratings currently in effect.

06/30/2005 09:55AM

Jun. 30. 2005 9:35AM CLECO PGO 6 FAX

No. 6339 P. 4

7. Tangible net worth (If any portion of the closure and/or post closure cost estimates is included in the "total liabilities" in your firm's financial statements, you may add that portion to this line) \$ 439,695,000

8. Total assets in the U.S. (required only if less than 90% of assets are located in the U.S.):

NOT APPLICABLE

	<u>YES</u>	<u>NO</u>
9. Is line 7 at least \$10 million?	X	
10. Is line 7 at least 6 times line 3?	X	
11. Are at least 90% of assets located in the U.S.? If not, complete line 12.	X	
12. Is line 8 at least 6 times line 3?	N/A	

I hereby certify that the wording of this letter is identical to the wording specified in LAC 33:VII.727-A.2.i.iv.(c).

Yours very truly,

CLECO POWER LLC


BY: Dilek Samil
Dilek Samil
Sr. Vice President & Chief Financial Officer

Date: 3-30-2005

cc: Mr. Doug Beck - PricewaterhouseCoopers LLP

06/30/2005 09:55AM

Cleco Corporation
2005 Summary Review



Memorable Year

Last year was memorable for one obvious reason: the devastation wrought by hurricanes Katrina and Rita on Louisiana and the Gulf Coast. Just as unforgettable were the efforts of tens of thousands of volunteers who came from across the nation to help our local officials start rebuilding their communities.

These deadly storms left significant numbers of our customers without power for days on end and posed a challenge for our employees as they worked to repair heavily damaged transmission and distribution systems. Their efforts exceeded all expectations. It earned Cleco another national award for storm restoration work. Gulf Coast residents are still feeling the effects of Katrina and Rita, but we're quickly getting back on our feet.

Not to be overlooked is the progress Cleco made during 2005 toward achieving key objectives, such as securing a reliable, stable-priced source of power for our customers, continuing our highly active role in economic development throughout our service territory, and positioning

ABOUT THE COVER

The year 2005 was made memorable by a thousand small stories that left an indelible impression on everyone affected by the year's storms. For example, Alexandria Senior High softball coach Mark Rosier (far right) and leaders of Alexandria Dixie Girls Softball saw a need to help hurricane victims. Within seven days, they organized a 28-team tournament that raised \$3,200 for storm victims. Athletes from across central Louisiana donated their time, including (from left) Jill Paulk of Pineville, Hillary LaCroix of Alexandria, Amy Phillips of Woodworth, and Patricia Whittine of Alexandria.

our company as a leader in customer satisfaction and service reliability. Indeed, perhaps our most notable achievement in 2005 was being able to devote extraordinary resources to hurricane recovery while executing our long-term strategies.

It is more important than ever that we continue to focus on building lasting value for our customers and our shareholders. The following pages offer some examples of our initiatives and how they helped make 2005 one very memorable year.



Relentless Focus

Building a reliable, environmentally sound power source for Louisiana is at the heart of our strategy to meet customers' long-term needs for affordable electricity. The planned \$1 billion investment in a 600-megawatt solid-fuel unit at our Rodemacher Power Station will diversify our fuel mix and enable us to cut customers' costs. It will help ambitious Louisiana entrepreneurs such as Allen and Marie Davis, owners of New Iberia's Taste N Sea restaurant, expand their business and create jobs. "We have the same goal as Cleco," Allen said. "We want to give customers the best service possible at an affordable price. It's how you build a lasting business." And it's why Cleco sees the new Rodemacher unit as the foundation for our company's long-term growth. Our plans call for the unit, which will incorporate the fuel flexibility of circulating fluidized-bed technology, to be under construction in the spring of 2006 and operational in late 2009.



Vision for Louisiana

Developing a strong, diverse economy for Louisiana is a priority. It's not without challenges, but Cleco is working to make that vision a reality across our service territory. Through long-standing partnerships with public and private entities, we expect to continue building on our accomplishments. We've been a key player in persuading a number of businesses to expand and others to locate in our region. Perhaps the biggest achievement was helping bring Union Tank Car Co. and its 850 jobs to central Louisiana. In fact, an article in the May 2005 edition of *Site Selection* magazine listed the Union Tank Car plant as one of the top 10 economic development deals in the nation for 2004. The same magazine followed up that article in September 2005 by ranking Cleco one of the top 10 utilities in the country because of our 2004 success in attracting total investment and new jobs on a per capita basis. With the economic development and industrial marketing work we've done over the last two years, we will have added roughly 55 megawatts of new load to our system by 2007. Economic development obviously expands our business, but it means more than that to us. It's part of our commitment to the communities we serve.



Customer at a Time


Our customers want and deserve excellent service and reliability. That's what we deliver — all day, every day. It comes down to building good relationships, knowing our customers' individual needs, and making sure we meet them. Reliability and superior power quality are crucial for the advanced biomedical research conducted at the Tulane National Primate Research Center in St. Tammany Parish, for example. By working together, we help ensure operations at the center continue uninterrupted. Providing outstanding service to residential customers such as the Robinson family of Pineville is just as important. It's why we're constantly working to improve our performance. The average duration of outages dropped by roughly 30 percent during 2005 — not counting the hurricanes — and again easily beat state standards. We also live up to our commitment to serve the needs of all of our customers. In 2005, we donated \$200,000 to community action agencies across our service territory to help customers struggling to meet the rising costs of energy and other necessities. We also gave more than \$425,000 to various local charities and organizations.





Unforgettable Month

Hurricanes Katrina and Rita were catastrophes that tested the resources of our company and the resolve of our employees. Just as we were close to wrapping up restoration work after the devastating blow Katrina dealt our service area north of New Orleans on Aug. 29, Rita struck Sept. 24, hitting every part of our service territory. The numbers tell the story: 29 days to restore power to 86,403 customers affected by Katrina; 14 days to restore lights to 136,584 customers affected by Rita; 378,622 calls to our call center; 6,022 poles replaced; 3,032 transformers replaced; 4,230 miles of distribution lines repaired or replaced; 612 miles of transmission line reenergized; 2,878 employees and contractors repaired damage from Katrina; 2,435 employees and contractors repaired damage from Rita; and \$300,000 was donated by the company — along with thousands more from employees and national and international donors — to create the Cleco EmPowers Fund for storm victims. Our employees once again showed their determination and dedication when faced with a challenge. As one person wrote in a note of thanks: "Our hats are off to Cleco and crews for a monumental job well done."



of the Nation's Best

Cleco's customer satisfaction ranked among the best in the country, according to a 2005 national survey of residential customers. It's the third year in a row we finished among the top investor-owned utilities. You don't achieve results like that without extraordinary employees such as Nate Wilson, lead line mechanic in the Slidell area. In addition, during 2005 the nation's retail chains named Cleco among the utilities that offer the best overall customer service. Our own research backs up the honors. The number of very satisfied Cleco customers was 16 points higher for Cleco than for the average Louisiana utility. But we're not satisfied yet. Every employee is committed to building trust, to delivering on our promises, and to taking extra steps so we can better meet all of our customers' needs.

LETTER TO SHAREHOLDERS

Dear Shareholders,

For everyone in Louisiana, 2005 was indeed a memorable year. Facing unprecedented challenges posed by hurricanes Katrina and Rita, Louisiana residents and Cleco employees demonstrated an amazing resilience.

Hundreds of our employees joined outside contractors to create a team of thousands who worked nonstop over six weeks to restore power to more than 220,000 customers affected by the storms. It was the largest restoration effort in our company's history, and it earned Cleco national recognition. We received the Edison Electric Institute's (EEI) prestigious Emergency Response Award. This was the fourth straight year our peers honored us for storm response work.

It is wonderful to be recognized nationally, but we are even more proud to be honored locally. We were named business of the year by the St. Tammany West Chamber of Commerce. That honor was particularly meaningful, because it was given by our hardest-hit customers.



Michael H. Madison
President and
Chief Executive Officer
Cleco Corporation

LETTER TO SHAREHOLDERS

Even with the extraordinary events of 2005, we accomplished major objectives, tackled a variety of issues, and continued executing our strategy for long-term growth.

My pride in being part of this company increases each day, as does my confidence in the abilities of my co-workers to carry out our plans.


We begin 2006 with straightforward objectives.

- Moving ahead with a \$1 billion investment in a new solid-fuel generating unit to diversify our fuel mix and provide customers with lower, more stable fuel costs
- Building on our superior customer service
- Expanding the utility through economic development
- Maintaining our financial strength

My belief in our ability to carry out our plans is firmly rooted in my appreciation of the expertise and leadership skills of our management team. It's been almost a year since I took over as Cleco's president and chief executive officer, and I've had the good fortune to have Dilek Samil, our former chief financial officer, running our regulated utility and Kathleen Nolen, our former treasurer, serving as chief financial officer. Their experience and hard work, along with the talents of our entire work force, helped make this challenging year a success.

Among 2005 events, we:

- Earned \$3.53 per diluted share, \$1.42 per share excluding the earnings from the Perryville transactions explained below.
- Completed the sale of both the Perryville plant and our claims in the related Mirant bankruptcy case, which, net of the project's losses since January 2004, contributed \$2.11 per diluted share toward 2005 earnings. If you'll recall, we posted impairment charges associated with Perryville of \$1.94 per share in 2003. We're proud of the value we were able to capture from Perryville given the obstacles we faced along the way.
- Improved financial strength by reducing debt \$395 million over the last three years, including project-related debt.
- Continued to offer solid, long-term value to shareholders. On a 10-year basis, our stock's total return performance is in line with the major utility indices and better than the Standard & Poor's 500. (See "Total Return" chart above.)
- Finished 2005 in the top quartile of all EEI companies for lowest rate of personal injuries and vehicle collisions. It was the sixth straight year our incident rate of Occupational Safety and Health Administration-recordable injuries put us in EEI's top quartile. Helping us reach that achievement were employees at our Teche Power Station and Patterson Work Center who completed an amazing 18 years and 17 years, respectively, without a lost-time injury. It's that kind of dedication to safety we're trying to instill across Cleco through our Target Zero program.
- Initiated efforts to limit the impact of the late December bankruptcy filing of Calpine Corp., our partner in the Acadia power plant. Calpine Energy Services, L.P.'s request in bankruptcy court to reject the Acadia tolling agreements is pending as this letter is being written; however, we are working to offset the effect of any such action. The partnership restructurings we put in place in 2003 and 2005 will help enhance Cleco's value in the plant assuming we must market its output.
- Worked to manage fuel costs in the face of record high natural gas prices. We relied heavily on our Dolet Hills Power Station and Rodemacher Power Station solid-fuel units. Their equivalent availability factor was a combined 87.39 percent in 2005, superior to industry standards. These plants consistently meet or beat industry availability benchmarks, which include many units that use higher grades of coal and have less complex environmental controls.



LETTER TO SHAREHOLDERS

Fuel Diversity

Even with the good performance of our solid-fuel plants, two-thirds or more of the electricity Cleco sells is produced from or directly tied to natural gas. Although the hurricanes contributed to a tremendous run-up in natural gas prices, it's clear that Cleco and Louisiana need to reduce a long-standing reliance on natural gas. We cannot allow our residential customers and Louisiana businesses to be so heavily dependent on a fuel with a price expected to remain high and volatile well into the future. We must increase our fuel diversity.

That's why we're moving ahead with plans to construct a 600-megawatt solid-fuel unit — among the cleanest units of its type in the nation — at our Rodemacher plant near Boyce, La. The proposed project is the result of a solicitation process overseen by an independent monitor and completed in consultation with the staff of the Louisiana Public Service Commission (LPSC). The project has earned support from a variety of community and political leaders.

Benefits for Louisiana

Our \$1 billion investment offers both a short- and long-term economic benefit for Louisiana. We've contracted with a subsidiary of Louisiana-based The Shaw Group to build the plant. And we expect 1,200 people to be employed at the peak of construction. That's in addition to the approximately 80 people we anticipate hiring to run the unit. But the key to the project is the expected future fuel savings our customers will realize. We believe the plant will lower our customers' costs, strengthen Cleco's competitive position, and provide a long-term platform for the growth of our company and our service area.

The unit's circulating fluidized-bed technology will give it the flexibility to burn a variety of fuels. But our primary fuel of interest is petroleum coke, or pet coke. A byproduct of the oil refining process, pet coke is produced in abundant quantities in Louisiana and the Gulf Coast region. We are exploring the possibility of barging pet coke along Louisiana's rivers, helping fulfill the economic promise of the Red River.

LPSC Approval


We have received final LPSC approval of our plan to build the unit, and we are working to wrap up outstanding issues so construction can start in April. The lack of opposition to our air permit application speaks to the effectiveness of the environmental controls in our design. We are proud of the progress we've made on the environmental front and proud of the affirmation by our regulators that our plan is what's best for customers.

We believe the LPSC's decision to allow us to recover an amount equal to approximately 75 percent of the carrying costs of funds used to build the unit is an example of the regulatory commitment to diversifying the state's fuel mix. And their approval of a plan allowing us to recover our storm restoration costs over a 10-year period shows their understanding of our financial needs while we build the unit.

In order to balance customer and shareholder interests, the LPSC staff proposed modifications to our rate plan in its recommendation for approval of the project and recovery of storm costs. Our maximum regulated rate of return on equity will be 12.25 percent through Sept. 30, 2006. From that point through the start of plant operations, currently expected to be in late 2009, the staff-proposed regulated return on equity will be set at 11.25 percent. After Oct. 1, 2006, the staff's plan creates a mechanism for us to return to customers 60 percent of earnings between 11.25 percent and 12.25 percent. Customers will receive all earnings above the 12.25 percent level. Although our rate plan will change, the proposal still provides a

EARNINGS AND DIVIDENDS

In dollars (per diluted share)



* Excluding the \$2.11 per share impact of the reconsolidation of Perryville, Cleco Corporation would have earned \$1.42 per share for 2005.

LETTER TO SHAREHOLDERS

2006 Top Goals

1. Start construction of \$1 billion solid-fuel unit.
2. Provide value to customers through superior reliability and customer service.
3. Expand the utility through economic development.
4. Maintain our investment-grade credit rating.
5. Continue our emphasis on safety.

2005 Top Accomplishments

1. Honored for superior performance recovering from hurricanes Katrina and Rita.
2. Completed sale of both the Perryville plant and Mirant bankruptcy claims.
3. Ranked among the nation's best in customer satisfaction and service.
4. Made progress toward increasing fuel diversity through plans for a new generating unit.
5. Strengthened financial condition.

competitive return. We expect the LPSC to take up the matter in the near future.

The expansion at our Rodemacher plant will be the biggest project in Cleco's history. It will require an extraordinary commitment of resources.


Although that investment is large, you can be certain our company will continue to fund prudent expenditures to improve the performance, safety, and reliability of our existing system. A good example is the Wells Substation. We joined with another utility to invest approximately \$20 million building a transmission substation to strengthen the reliability of the south Louisiana grid. Thanks to the work of our transmission group, the substation was completed well ahead of schedule, and its performance has exceeded all expectations.

Our employees exceed all expectations too. Their creativity and work ethic are unmatched. They thrive on challenges. The year's storms amplified those traits and provided many examples of our employees' kindness and commitment to helping the people we serve. Dozens of employees whose own homes were damaged by the storms set aside their problems to restore power to their communities. That created a sense of hope for friends and neighbors surrounded by destruction. It is a privilege to work with such people.

I also consider it an honor to have worked with David Eppler, who retired as president and CEO in mid-2005. David's energy and intelligence contributed greatly to Cleco's success during his 23 years with the company. In addition, I would like to give my thanks to Ray Nesbitt, who is leaving our board of directors at our annual meeting, having reached the mandatory retirement age of 72. His expertise has been invaluable to Cleco since he joined the board in 2001.

The wise guidance of our board and the hard work and dedication of our employees allow us to build on Cleco's long record of delivering value to our customers and shareholders.

Thank you for your continued investment and confidence in our future.



Michael H. Madison
President and Chief Executive Officer
Cleco Corporation

Feb. 28, 2006

CLECO CORPORATION

Financial Highlights

(DOLLARS IN THOUSANDS)	YEAR ENDING DEC. 31			5-YEAR
	2005 (1)	2004 (2)	2003 (3)	COMPOUND %CHANGE
Financial Data				
Total operating revenue, net	\$ 920,154	\$ 745,817	\$ 803,452	6.63 %
Operating income (loss)	\$ 111,734	\$ 101,138	\$ (11,547)	(5.23)%
Equity income from investees	\$ 218,441	\$ 47,250	\$ 31,391	—
Net income (loss) applicable to common stock	\$ 180,779	\$ 63,973	\$ (36,790)	23.43 %
Consolidated total assets	\$ 2,149,488	\$ 1,837,063	\$ 2,159,426	4.19 %
Capital expenditures	\$ 187,393	\$ 79,873	\$ 74,511	(2.31)%
Consolidated long-term debt as percentage of capitalization	46.33 %	44.54 %	64.40 %	(4.35)%
Shareholder Value				
Average shares of common stock outstanding, basic	49,486,790	47,371,319	46,820,058	1.94 %
Average shares of common stock outstanding, diluted	51,760,220	47,528,886	46,820,058	2.83 %
Earnings (loss) per share, basic	\$ 3.54	\$ 1.33	\$ (0.79)	21.09 %
Earnings (loss) per share, diluted	\$ 3.53	\$ 1.32	\$ (0.79)	21.02 %
Dividends paid per common share	\$ 0.900	\$ 0.900	\$ 0.900	1.27 %
Return on average common equity	29.4 %	12.5 %	(7.0)%	16.00 %
Book value per average common share	\$ 13.87	\$ 11.44	\$ 10.31	6.05 %
Market price at year-end	\$ 20.85	\$ 20.26	\$ 17.98	(5.30)%
Dividend yield at year-end	4.3 %	4.4 %	5.0 %	6.76 %

Consolidated Diluted Earnings (Loss) Per Share
Allocated to Subsidiaries

	YEAR ENDING DEC. 31		
	2005	2004	2003 (3)
Subsidiary			
Cleco Power LLC	\$ 1.15	\$ 1.08	\$ 1.22
Cleco Midstream Resources LLC	\$ 2.39	\$ 0.37	\$ (1.72)
Other (including Corporate)	\$ (0.01)	\$ (0.13)	\$ (0.18)
Consolidated earnings (loss) from continuing operations allocated to subsidiaries	\$ 3.53	\$ 1.32	\$ (0.68)
Discontinued operations	\$ —	\$ —	\$ (0.11)
Net earnings (loss) applicable to common stock	\$ 3.53	\$ 1.32	\$ (0.79)

(1) The deconsolidation of Perryville Energy Partners, LLC, and Perryville Energy Holdings LLC (PEH) from Cleco in connection with their bankruptcy filings affected Midstream's earnings for 2004 compared to 2003, since no income or loss associated with those subsidiaries was recognized in Midstream's consolidated financial statements subsequent to the bankruptcy filing on Jan. 28, 2004. An order confirming PEH's and Perryville's plan of reorganization became effective Oct. 11, 2005. As a result, Cleco recorded its investment in Perryville on the equity method of accounting and PEH's results from Jan. 28, 2004, to Oct. 11, 2005, were reconsolidated with Cleco. Perryville's revenue and expenses from Jan. 28, 2004, to Oct. 11, 2005, were netted and reported as equity income from investees on Cleco Corporation's Consolidated Statements of Operations. Perryville's assets and liabilities are represented by one line item corresponding to Cleco's investment in Perryville on Cleco Corporation's Consolidated Balance Sheets.

(2) Cleco deconsolidated Evangeline from its financial statements and began reporting its investment in Evangeline on the equity method of accounting. As a result, effective March 31, 2004, the assets and liabilities of Evangeline are no longer reported on Cleco Corporation's Consolidated Balance Sheets, but instead are represented by one line item corresponding to Cleco's equity investment in Evangeline. Effective April 1, 2004, Evangeline revenue and expenses are netted and reported as equity income from investees on Cleco Corporation's Consolidated Statements of Operations.

(3) 2003 results include asset-impairment charges associated with the Perryville project, which totaled \$91.0 million after-tax, or \$1.94 per share.

CLECO CORPORATION

Five-Year Selected Financial Data (Unaudited)

(THOUSANDS, EXCEPT SHARE, PER SHARE, PERCENTAGES, AND RATIOS)	2005	2004	2003	2002	2001
Operating revenue (excluding intercompany revenue)					
Cleco Power	\$ 911,971	\$ 727,449	\$ 705,079	\$ 593,781	\$ 622,722
Midstream	4,984	14,844	97,129	98,693	64,791
Other	3,199	3,524	1,244	57	113
Total	\$ 920,154	\$ 745,817	\$ 803,452	\$ 692,531	\$ 687,626
Total operating expenses (excluding fuel and power purchases)	\$ 233,838	\$ 223,259	\$ 418,287	\$ 234,431	\$ 221,022
Allowance for funds used during construction	\$ 1,446	\$ 2,478	\$ 1,928	\$ 2,116	\$ (409)
Federal and state income tax expense (benefit)	\$ 115,951	\$ 35,864	\$ (21,417)	\$ 39,665	\$ 39,170
Income (loss) from continuing operations before income taxes	\$ 298,929	\$ 101,983	\$ (51,185)	\$ 120,038	\$ 113,657
Net income (loss) applicable to common stock	\$ 180,779	\$ 63,973	\$ (36,790)	\$ 70,003	\$ 68,362
Basic earnings (loss) per share from continuing operations	\$ 3.54	\$ 1.33	\$ (0.68)	\$ 1.65	\$ 1.57
Basic earnings (loss) per share applicable to common stock	\$ 3.54	\$ 1.33	\$ (0.79)	\$ 1.47	\$ 1.47
Diluted earnings (loss) per share from continuing operations	\$ 3.53	\$ 1.32	\$ (0.68)	\$ 1.65	\$ 1.56
Diluted earnings (loss) per share applicable to common stock	\$ 3.53	\$ 1.32	\$ (0.79)	\$ 1.47	\$ 1.47
Return on average common equity	29.4 %	12.5 %	(7.0) %	13.3 %	14.3 %
Effective tax rate	38.8 %	35.2 %	41.8 %	33.0 %	34.5 %
Capital expenditures (adjustments of)					
Cleco Power	\$ 186,441	\$ 78,700	\$ 68,507	\$ 87,321	\$ 45,642
Midstream	13	(142)	4,843	98,064	136,284
Other (after allocation to Cleco Power and Midstream)	939	1,315	1,161	(1,260)	529
Total	\$ 187,393	\$ 79,873	\$ 74,511	\$ 184,125	\$ 182,455
Internal cash generation (% of capital expenditures)					
Cleco Power	67.0 %	100.0 %	100.0 %	100.0 %	100.0 %
Midstream	100.0 %	100.0 %	100.0 %	56.4 %	19.2 %
Other	100.0 %	100.0 %	100.0 %	100.0 %	100.0 %
Property, plant and equipment, net — Cleco Power					
Production	\$ 178,214	\$ 192,456	\$ 199,013	\$ 209,765	\$ 218,802
Transmission	\$ 257,385	\$ 250,473	\$ 248,003	\$ 243,986	\$ 236,009
Distribution	\$ 640,924	\$ 493,119	\$ 476,183	\$ 460,636	\$ 428,477
Other	\$ 104,012	\$ 115,147	\$ 105,506	\$ 98,693	\$ 93,661
Capitalization					
Common shareholders' equity	52.15 %	53.56 %	34.27 %	38.83 %	43.36 %
Preferred stock	1.52 %	1.90 %	1.33 %	1.21 %	1.41 %
Long-term debt	46.33 %	44.54 %	64.40 %	59.96 %	55.23 %
Common shareholders' equity	\$ 686,229	\$ 541,838	\$ 482,750	\$ 562,470	\$ 491,966
Preferred stock	\$ 20,034	\$ 19,226	\$ 18,717	\$ 17,508	\$ 15,988
Long-term debt	\$ 609,643	\$ 450,552	\$ 907,058	\$ 868,684	\$ 626,778
Short-term debt	\$ 40,000	\$ 160,000	\$ 205,705	\$ 360,701	\$ 210,398
Total consolidated debt	\$ 649,643	\$ 610,552	\$ 1,112,763	\$ 1,229,385	\$ 837,176
Equity investment in investees	\$ 317,762	\$ 314,284	\$ 264,073	\$ 272,991	\$ 226,427
Total assets	\$2,149,488	\$1,837,063	\$2,159,426	\$2,344,556	\$1,767,890
Total liabilities	\$1,443,225	\$1,275,999	\$1,657,958	\$1,764,578	\$1,301,549
Embedded cost of debt	6.49 %	7.29 %	7.15 %	6.67 %	8.08 %
Ratio of earnings to fixed charges (pre-tax)	6.31	2.95	0.43	2.65	2.77
Total return to shareholders	7.2 %	18.3 %	35.9 %	(32.9) %	(16.5) %
Average shares outstanding for year, basic	49,486,790	47,371,319	46,820,058	46,245,104	45,000,955
Average shares outstanding for year, diluted	51,760,220	47,528,886	46,820,058	46,292,058	47,763,713
Market price per share at year-end	\$ 20.85	\$ 20.26	\$ 17.98	\$ 14.00	\$ 21.97
Market capitalization at year-end	\$1,036,745	\$ 997,521	\$ 843,244	\$ 658,490	\$ 987,793
Price-earnings ratio at year-end	5.9	15.2	(22.8)	9.5	15.0
Market-to-book ratio at year-end	1.5	1.8	1.7	1.2	2.0
Book value per share at year-end	\$ 13.87	\$ 11.44	\$ 10.31	\$ 12.16	\$ 10.93
Cash dividends paid per common share	\$ 0.900	\$ 0.900	\$ 0.900	\$ 0.895	\$ 0.870
Dividend payout ratio	25.4 %	67.7 %	(113.9) %	61.2 %	59.2 %
Dividend yield at year-end	4.3 %	4.4 %	5.0 %	6.4 %	4.0 %

CLECO CORPORATION


Five-Year Selected Operating Data (Unaudited)

(THOUSANDS, EXCEPT PERCENTAGES AND RATIOS)	2005	2004	2003	2002	2001
Nonfuel recovery revenue by customer class — Cleco Power					
Residential	\$154,928	\$153,607	\$149,755	\$148,544	\$140,547
Commercial	70,547	70,116	67,950	66,212	64,127
Industrial	54,966	54,978	55,098	55,033	52,578
Other	41,360	39,284	37,964	34,400	29,641
Unbilled	622	48	1,212	1,194	1,012
Total	\$322,423	\$318,033	\$311,979	\$305,383	\$287,905
Sales of electricity (millions of kilowatt-hours) — Cleco Power					
Residential	3,516	3,507	3,429	3,400	3,201
Commercial	1,838	1,854	1,781	1,722	1,655
Industrial	2,861	2,902	2,786	2,756	2,640
Other retail	610	597	595	593	581
Unbilled	18	(3)	39	30	34
Total retail	8,843	8,857	8,630	8,501	8,111
Sales for resale	552	1,057	1,066	715	398
Total retail and wholesale customer sales	9,395	9,914	9,696	9,216	8,509
Average retail customers by class — Cleco Power					
Residential	227,799	225,949	221,778	219,503	216,809
Commercial	32,161	31,937	31,429	30,477	29,749
Industrial	674	692	700	712	722
Other	6,401	6,272	6,210	6,153	6,113
Total	267,035	264,850	260,117	256,845	253,393
Average revenue per kWh sold — Cleco Power					
Residential	\$ 0.1009	\$ 0.0850	\$ 0.0815	\$ 0.0729	\$ 0.0814
Commercial	\$ 0.0952	\$ 0.0788	\$ 0.0760	\$ 0.0675	\$ 0.0764
Industrial	\$ 0.0722	\$ 0.0567	\$ 0.0541	\$ 0.0466	\$ 0.0553
Other, including unbilled	\$ 0.1171	\$ 0.0664	\$ 0.0649	\$ 0.0566	\$ 0.0583
Total composite	\$ 0.0931	\$ 0.0724	\$ 0.0697	\$ 0.0616	\$ 0.0696
Average annual kWh use per residential customer — Cleco Power					
	15,435	15,521	15,461	15,490	14,764
Average annual revenue per residential customer — Cleco Power					
	\$ 1,557	\$ 1,319	\$ 1,260	\$ 1,129	\$ 1,202
Degree-days — % change from normal:					
Heating	(17.2)%	(9.9)%	7.8 %	7.7 %	(4.8)%
Cooling	15.8 %	4.0 %	(2.3)%	4.0 %	(1.1)%
Capacity (MW)					
Cleco Power:					
Coal and lignite	482	482	482	482	482
Natural gas and oil	877	877	877	877	880
Firm capacity purchases	671	831	857	857	772
Midstream:					
Natural gas — 718-MW sold in 2005	1,355	2,073	2,073	2,061	848
Total	3,385	4,263	4,289	4,277	2,982
Peak demand (MW) — Cleco Power					
	2,014	1,940	1,990	1,937	1,850
Generation (MWh) — Cleco Power					
Net generation — system plants	5,284	4,820	5,044	5,405	5,536
Purchased power	5,028	5,592	5,134	4,482	3,739
Total energy supply	10,312	10,412	10,178	9,887	9,275
Cost of fuel per kWh					
	\$ 0.0588	\$ 0.0404	\$ 0.0375	\$ 0.0285	\$ 0.0358
Fuel Mix — Cleco Power					
Coal and lignite	33.9 %	31.6 %	31.9 %	32.6 %	33.0 %
Natural gas and oil	17.3 %	14.7 %	17.7 %	22.0 %	26.7 %
Purchased power	48.8 %	53.7 %	50.4 %	45.4 %	40.3 %
System annual load factor	57.2 %	60.0 %	58.2 %	59.5 %	57.2 %
System Average Interruption Duration Index (SAIDI) — Cleco Power					
(Average number of hours a customer's service is interrupted)	1.86	2.75	2.45	2.82	2.40
System Average Interruption Frequency Index (SAIFI) — Cleco Power					
(Average number of times a customer's service is interrupted)	1.86	2.02	1.94	2.09	1.82
Customer Satisfaction Percentage — Cleco Power					
	91 %	91 %	92 %	93 %	92 %
Number of employees					
	1,158	1,165	1,203	1,214	1,392

Financial Data (As of Dec. 31, 2005)


LONG-TERM DEBT

In millions of dollars



BOOK VALUE PER SHARE AT YEAR END


In dollars



Operating Data (As of Dec. 31, 2005)


SALES OF ELECTRICITY CLECO POWER

In millions of kilowatt hours



AVERAGE REVENUE PER KWH SOLD CLECO POWER

In dollars



Company Profile


Cleco Corporation (NYSE: CNL), based in Pineville, La., is a regional energy services provider with two primary businesses: Cleco Power LLC, a regulated electric utility, and Cleco Midstream Resources LLC, a wholesale generation subsidiary.

Today, Cleco Power serves approximately 267,000 customers across Louisiana. It owns approximately 1,360 megawatts of regulated generating capacity.

Cleco Midstream has approximately 1,350 megawatts of wholesale generation assets in operation.

CLECO POWER FUEL SOURCES

- Coal and lignite
- Natural gas and oil
- Purchased power



Energy Assets and Operations


REGULATED GENERATION CLECO POWER LLC

	TOTAL CAPACITY (MW)	OWNERSHIP (PERCENT)	FUEL SOURCE
1 Dolet Hills	650	50	lignite
2 Rodemacher			
Unit 1	440	100	gas/oil
Unit 2	523	30	coal/gas
3 Teche	430	100	gas/oil

WHOLESALE GENERATION CLECO MIDSTREAM RESOURCES LLC

	TOTAL CAPACITY (MW)	OWNERSHIP (PERCENT)	FUEL SOURCE
4 Acadia	1,160	50	gas
5 Evangeline	775	100	gas

Cleco Service Territory



Board of Directors (As of Dec. 31, 2005)

Sherian G. Cadoria

Age 65; Elected 1993
Brigadier General,
U.S. Army (retired)
Retired President,
Cadoria Speaker and
Consultancy Service, Mansura, La.
*Member of the Audit,
Nominating/Governance
and Qualified Legal
Compliance committees*

Richard B. Crowell

Age 67; Elected 1997
Partner, law firm of Crowell
& Owens, Alexandria, La.
*Member of the Audit, Nominating/
Governance and Qualified Legal
Compliance committees*

J. Patrick Garrett

Age 62; Elected 1981
Retired President and
Chief Executive Officer, Windsor
Food Co., Ltd., Houston, Texas
*Chairman of the board and
chairman of the Executive,
Nominating/ Governance
and Qualified Legal
Compliance committees*

F. Ben James Jr.

Age 69; Elected 1986
President, James Investments Inc.
(real estate development and
international marketing),
Ruston, La.
*Member of the Audit and
Compensation committees*

Elton R. King

Age 59; Elected 1999
Retired President of network
and carrier services group,
BellSouth Telecommunications
Inc., Atlanta, Ga. Also retired
President and CEO of Visual
Networks Inc.
*Member of the Compensation
and Finance committees*

Michael H. Madison

Age 57; Elected 2005
President and
Chief Executive Officer,
Cleco Corp.
*Member of the
Executive Committee*

William L. Marks

Age 62; Elected 2001
Chairman and Chief Executive
Officer, Whitney Holding Corp.
and Whitney National Bank,
New Orleans, La.
*Chairman of the Finance
Committee and member
of the Executive and
Compensation committees*

Ray B. Nesbitt

Age 72; Elected 2001
Retired President of Exxon
Chemical Co., Houston, Texas
*Member of the Compensation,
Finance, Nominating/Governance
and Qualified Legal Compliance
committees*

Robert T. Ratcliff Sr.

Age 63; Elected 1993
Chairman, President and
Chief Executive Officer,
Ratcliff Construction
Company LLC, Alexandria, La.
*Member of the Audit,
Nominating/Governance
and Qualified Legal
Compliance committees*

William H. Walker Jr.

Age 60; Elected 1996
Retired Chairman of Howard
Weil Inc., New Orleans, La.
*Chairman of the Compensation
Committee and member of the
Executive and Finance committees*

W. Larry Westbrook

Age 66; Elected 2003
Retired Chief Financial Officer
and Senior Risk Officer of
Southern Company, Atlanta, Ga.
*Chairman of the Audit Committee
and member of the Executive and
Finance committees*

Officers (As of Dec. 31, 2005)

EXECUTIVE MANAGEMENT TEAM



Michael H. Madison

Age 57;
Joined Cleco in 2003
President and Chief Executive
Officer, Cleco Corp.
Chief Executive Officer,
Cleco Power LLC



Kathleen F. Nolen

Age 45;
Joined Cleco in 1983
Senior Vice President
and Chief Financial Officer



Samuel H. Charlton III

Age 60;
Joined Cleco in 1997
Senior Vice President and
Chief Operating Officer,
Cleco Midstream Resources LLC



Dilek Samil

Age 50;
Joined Cleco in 2001
President and Chief Operating
Officer, Cleco Power LLC



George W. Bausewine

Age 50;
Joined Cleco in 1986
Senior Vice President,
Corporate Services



Douglas A. Bell

Age 51;
Joined Cleco in 1989
General Manager, Internal Audit
Cleco Support Group LLC



R. O'Neal Chadwick Jr.

Age 45;
Joined Cleco in 2000
Senior Vice President
and General Counsel

OTHER OFFICERS

Anthony L. Bunting

Age 46; Joined Cleco in 1992
Vice President of Customer
Services and Energy Delivery,
Cleco Power LLC

Stephen M. Carter

Age 46; Joined Cleco in 1988
Vice President of
Regulated Generation,
Cleco Power LLC

R. Russell Davis

Age 49; Joined Cleco in 2000
Vice President and
Chief Accounting Officer

Jeffrey W. Hall

Age 54; Joined Cleco in 1981
Vice President of Governmental
& Community Affairs

Mark H. Segura

Age 47; Joined Cleco in 1984
Vice President of Transmission
& Distribution Services,
Cleco Power LLC

William G. Fontenot

Age 42; Joined Cleco in 1986
Vice President of Regulated
Generation Development,
Cleco Power LLC

Keith D. Crump

Age 44; Joined Cleco in 1989
Treasurer

Judy P. Miller

Age 48; Joined Cleco in 1984
Corporate Secretary

Charles M. Murray

Age 45; Joined Cleco in 1986
Assistant Controller

Janice M. Mount

Age 62; Joined Cleco in 1984
Assistant Corporate Secretary

Shareholder Information

HEADQUARTERS

Cleco Corporation
2030 Donahue Ferry Road
P.O. Box 5000
Pineville, LA 71361-5000
(318) 484-7400
www.cleco.com

The Annual Meeting of Shareholders will be at 9 a.m. (Central time) on April 21, 2006, at the Best Western Inn and Suites and Convention Center of Alexandria, Plantation Room, 2720 West MacArthur Dr., Alexandria, La.

SHAREHOLDER ASSISTANCE

Toll-Free 1-800-253-2652
Representatives are available Monday through Friday, 8 a.m. to 5 p.m. (Central time).

Rodney J. Hamilton
Shareholder Relations Specialist

ANALYST CONTACTS

Keith D. Crump
Treasurer

Ryan T. Gunter
Manager of Investor Relations,
Strategy and Budget

SEND INQUIRIES TO

Post:
Shareholder Services
Cleco Corporation
P.O. Box 5000
Pineville, LA 71361-5000

E-mail:
investors@cleco.com

COMMON STOCK LISTING

Cleco Corporation common stock is listed on the New York Stock Exchange (symbol: CNL).

DIVIDEND SCHEDULE

Schedule of anticipated common stock dividend record and payment dates for 2006:

<u>Record Dates</u>	<u>Payment Dates</u>
Feb. 6	Feb. 15
May 1	May 15
July 31	Aug. 15
Oct. 30	Nov. 15

DIVIDEND REINVESTMENT

The dividend reinvestment plan enables shareholders to reinvest dividends on both common and preferred stock into additional shares of common stock. Shareholders can also purchase shares of common stock through an optional cash investment feature. A brochure describing the plan and an enrollment form are available from Shareholder Services or the transfer agent.

OTHER MATERIALS

Copies of the proxy statement, other SEC filings and other corporate publications are available on request from Shareholder Services and through our Web site.

NYSE CEO CERTIFICATION

Cleco has filed the certification of its chief executive officer and chief financial officer pursuant to Section 302 of the Sarbanes-Oxley Act of 2002 as exhibits to its Annual Report on Form 10-K for the year ended Dec. 31, 2005. In May 2005, Cleco's chief executive officer, as required by Section 303A.12(a) of the NYSE Listed Company Manual, submitted his certification to the NYSE that he was not aware of any violation by Cleco of the NYSE's corporate governance listing standards.

TRANSFER AGENT, REGISTRAR AND DIVIDEND AGENT

Common & Preferred Stock
Computershare Trust Company, N.A.
P.O. Box 43069
Providence, RI 02940-3069
Telephone: (781) 575-2723
www.computershare.com

TRUSTEE AND PAYING AGENT

Cleco Corporation Senior Notes
Cleco Evangeline LLC Bonds
J.P. Morgan Trust Company,
National Association
1999 Avenue of the Stars, 26th Floor
Los Angeles, CA 90067-6033

TRUSTEE AND PAYING AGENT

Cleco Power LLC Senior Notes
Cleco Power LLC Medium-Term Notes
Cleco Power LLC Retail Notes
The Bank of New York
Corporate Trust Administration
10161 Centurion Parkway
Jacksonville, FL 32256



Cleco Corporation
2030 Donahue Ferry Road
P.O. Box 5000
Pineville, LA 71361-5000
(318) 484-7400
www.cleco.com